



KTDC Hotels and Resorts Limited

(A Government of Kerala Undertaking)

Engineering Wing, Mascot Square, Thiruvananthapuram -695 033

Phone: 2318976, 2721243 Fax: ++91-471-2316168

E-mail: corporate@ktdc.com, website: www.ktdc.com

KTDC/EW/TEH/Mangattuparambu/2012

02-02-2012

QUOTATION NOTICE

Sub:-KTDC–Providing Compound Wall at Tamarind Easy Hotel, Mangattuparambu, Kannur–reg.

Competitive quotations are invited from reputed firms for Providing Compound Wall at Tamarind Easy Hotel, Mangattuparambu, Kannur as specified below.

Sl No	QTY		SPECIFICATION	UNIT	RATE	AMOUNT
1	10.00	m ³	Earth work excavation in ordinary soil and depositing on bank with initial lead upto 50m and lift upto 1.5m including breaking clods, watering, ramming and sectioning of spoil bank, etc.,. Complete. (Applicable to narrow excavations as in foundations of buildings etc.,)	10m ³		
2	2.00	m ³	Cement concrete 1:4:8 using 40mm (nominal size) broken stones.	m ³		
3	7.00	m ³	Laterite neatly dressed stones of size 30x20x17cm in cement mortar 1:5 for foundation.	m ³		
4	20.00	m ³	Laterite neatly dressed stones of size 30x20x17cm in cement mortar 1:5 for superstructure.	m ³		
5	1.60	m ³	Laterite neatly dressed stones of size 30X20X17cm in cement mortar 1:5 for cornices, copings etc.	m ³		
6	180	m ²	Pointing Laterite masonry with cement mortar 1:3.	10m ²		
7	30.00	m ²	Plastering with cement mortar 1:4, 15mm thick one coat on coping and cornice .	10m ²		

8	35.00	m ²	Finishing the walls with Antifungal Exterior Emulsion Asian/ Burger/ apex/ equivalent having approved colour 2 coats on new surface of external walls including priming coat using necessary scaffolding/rope/safety belt etc. after thoroughly cleaning with wire brush & water as directed. Work should be completed as per the direction of Engineer in charge.	10m ²		
9	35.00	kg	Providing and fixing vicat gate having 25mm dia.GI pipe outer frame and 12mm dia M.S square rods including all fittings like tower bolt, hinges, aldrop etc including cost of materials, labour, conveyance, fabricating and fixing charges, and applying a coat of iron primer.	q		
			TOTAL			

The rate shall be inclusive of all taxes, duties, loading and unloading, fixing charges transportation and other incidental expenses and net.

The offer shall reach the office of the Chief Engineer, KTDC Hotels & Resorts Ltd., Mascot Square, Trivandrum – 33 before **18-02-2012 up to 3PM** & the quotation will be opened at 4 PM on the same day.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.

CHIEF ENGINEER