



KTDC Hotels and Resorts Limited

(A Government of Kerala Undertaking)

Engineering Wing, Mascot Square, Thiruvananthapuram -695 033

Phone: 2318976, 2721243 Fax: ++91-471-2316168

E-mail: corporate@ktdc.com, website: www.ktdc.com

KTDC/EW/MA/Alappuzha/2011

29-12-2011

QUOTATION NOTICE

Sub:-KTDC –Miscellaneous works at the rear side of kitchen and construction of toilet at Motel Araam, Alappuzha– reg.

Competitive quotations are invited from reputed firms for the Miscellaneous works at the rear side of kitchen and construction of toilet at Motel Araam, Alappuzha as specified below.

NO	QTY		DISCRIPTION	UNIT		RATE	AMOUNT
1	1	m3	Dismantling, clearing away and carefully stacking materials useful for reuse for any thickness of walls of brick, laterite or rubble in cement mortar including disposal of debris within a distance of 150m.	1	m3		
2	2	m2	Demolishing and removing old cement plaster and Chipping the existing floor /wall to provide brick wall for the construction of toilet.	10	m2		
3	2	m3	Brick work in cement mortar 1:6 with country burnt bricks 19x9x9 cm for superstructure in ground floor upto 5m height. Including cost of materials, labour charges etc. complete	1	m3		
4	38	m2	Plastering with cement mortar 1:4, 12mm thick one coat including cost of materials, labour charges etc. complete.	10	m2		
5	184	dm3	Cement concrete 1:2:4 using 20mm (nominal size) broken stones for reinforced concrete work. Including the rate of form work but excluding the rate of reinforcement.	10	dm3		
6	8	kg	Reinforcement for RCC works, bent, tied and placed in position (plain grill requiring bending cold).	100	kg		

7	38	m2	Painting priming coat on new plastered surface after cleaning the surface.	10	m2		
8	1	no	Supplying and providing PVC door with frame for bath rooms including cost, labor for fixing including the fittings for door etc. complete	1	no		
9	10	m2	Dadoing walls with best quality glazed white or coloured tiles 7.5mm thick or nearest in 12mm cement mortar 1:3 and pointing with coloured cement.	1	m2		
10	4	m2	Supplying and paving ceramic flooring tiles of approved quality and colour setting in cement over a cement plastering using CM 1:3 12mm thick pointing the joints with suitable joint filler including all cost fixing charge and conveyance.	1	m2		
11	1	no	supplying and fixing European type water closet with P or S trap including seat cover, low level flush tank, flush pipe, angle cock, PVC connector etc including cost of materials, labour charges, fixing charges etc complete.	1	no		
12	10	m	supplying and providing 100 mm PVC pipes (8 kg/cm ²)for waste pipes including cost of materials labour for fixing etc. complete	1	m		
13	15	m	supplying and providing 25 mm CPVC pipes (12kg/cm ²)for water supply lines including cost of materials labour for fixing etc. complete	1	m		
14	1	no	Supplying and fixing Wash hand Basin 550 x 400 mm or nearest size of white glazed earthen ware with CI bracket , One central pillar tap 15 mm, PVC connector, angle cock, 32 mm brass waste including cost of materials, labour charges for fixing etc. complete.	1	no		
15	1	no	supplying and fixing shower with shower arm including cost of materials such as concealed stop cock	1	no		
16	1	no	Supplying and fixing exhaust fan 9" for providing at toilet	1	no		
17	2	nos	Supplying and fixing Long body CP tap	1	no		
18	1	m	Supplying and fixing health faucet with angle cock	1	m		

19	38	m2	Painting two coats with ready mixed plastic emulsion paint approved quality as specified and after cleaning the surface.	10	m2		
20	100	m2	Cleaning the fully shabby ceramic tiles at wall and floor tile cleaner/ acid including cost, labour charges etc.	10	m2		
21	4	m	Supplying and fixing teak wood reeper to fix the glass panels to the damaged windows	1	m		
22	2	m2	Supplying and fixing plain glass 3 mm thick in place of broken ones including cost of materials, labour for fixing etc	1	m2		
23	44	m2	Supplying and fixing false ceiling with PVC 12mm gypboard on GI frames both of INDIA GYPSUM .LTD, make as per the exact recommended profile for provision for accommodating Electrical and cove lighting requirements in the scheme to present a seamless finish including primer,2 coats of acrylic emulsion paint of approved colour including stepping ,POP moulding all cut outs for electrical fittings and including material cost ,labour charge ,etc. complete as per the direction of Engineer in charge.	1	m2		
24	21	m2	supplying and providing sun film to glass including cost of materials, labour for fixing etc complete	1	m2		
25	50	m2	Supplying and paving interlock concrete block (approximate size 15cm x 20cm) of approved brand and colour 50mm thick (15t/m2) as directed by the departmental officers over a bed of M' sand 75mm thick comparing using plate vibrator with lines and levels including all cost, conveyance of all materials and labour charge etc complete				
26	1	no	Shifting wash area of suitable place	1	E		
			GRAND TOTAL				-

The rate shall be inclusive of all taxes, duties, loading and unloading, fixing charges transportation and other incidental expenses and net.

The offer shall reach the office of the Chief Engineer, KTDC Hotels & Resorts Ltd., Mascot Square, Trivandrum – 33 before **13-01-2012 up to 3PM** & the quotation will be opened at 4 PM on the same day.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.

CHIEF ENGINEER