

## Kerala Tourism Development Corporation Ltd

(A Government of Kerala Undertaking)

Engineering Wing, Mascot Square, Thiruvananthapuram -695 033

Phone: 2318976, 2721243 Fax: ++91-471-2316168

E-mail: ce@ktdc.com website: www.ktdc.com

AE(E)II/KTDC.EW-TVM/556/WS-Kumarakom-AC/2019

08-04-2021

## **Short Quotation Notice**

Sub: - KTDC-Waterscapes, Kumarakom – Repositioning of outdoor units of split AC units installed in cottages - reg.

Competitive offers are invited from eligible and reputed firms for the Repositioning of outdoor units of split AC units installed in cottages at KTDC-Waterscapes, Kumarakom as per the schedule attached and the following terms and conditions.

## **Terms & Conditions**

- 1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
- 2. All statutory deduction will be deducted from the bill and exemption if any shall be informed with supporting documents.
- 3. The offer shall be valid for 30 days from the last date of submission of offers.
- 4. The work shall be carried within 10 days from the date of work order.
- 5. Satisfactory operation of the AC units shall be ensured after the repositioning work.
- 6. The quotations shall be enclosed and submitted in a sealed envelope on which the name of work shall be clearly superscribed. Otherwise the quotations will be summarily rejected.
- 7. Payment Terms- 100% payment will be passed on satisfactory completion of workat site.

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 33 on or before 16-04-2021, 2.30 PM.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.

P.K BABU

CHIEF ENGINEER

## REPOSITIONING OF OUTDOOR UNITS OF AIR CONDITIONING UNITS INSTALLED IN COTTAGES AT KTDC-WATERSCAPES, KUMARAKOM-BOQ

Sl. No.	Qty	Description	Rate	Unit	Amount
1	10	Dismantling of existing outdoor units (2.0TR) without any damages and reposition the same at required position including supply & fixing supporting stand / clamp for fixing the outdoor unit using suitable support bars /anchor bolts and safety hook up etc. including all accessories etc. complete.		Nos	
2	35	Supply & laying additional refrigerant lines (Both suction & discharge) using hard drawn copper pipe of the suitable sizes recommended by the manufacturer for 2.0TR AC unit including nitrile rubber thermal insulation of good quality to extend the refrigerant gas connection till outdoor unit as required at site.		m	
	J= -31	TOTAL (INCLUSIVE OF ALL TAXES & FREIGHT)		Rs	

A LIV

AEÈ(EL)

CEVER Jam