



Kerala Tourism Development Corporation Limited

(A Government of Kerala Undertaking)

P.B No.5424, Mascot Square, Vikas Bhavan P.O

Thiruvananthapuram –695 033, Kerala, India

Phone:++91-471- 2721243/45/48, Fax: 2721249

Website: www.ktdc.com

GST IN 32AABCK0385J1ZP

AE(E)II/KTDC.EW-TVM/982/HN-GVR-HT/2021

02.07.2024

Quotation Notice

Sub: - KTDC – Hotel Nandanam, Guruvayoor – Supply and Installation of HT metering equipment – reg.

Competitive offers are invited from eligible and reputed firms for the supply and installation of HT metering equipment at KTDC – Hotel Nandanam, Guruvayoor as per the schedule attached and the following terms and conditions.

Terms & Conditions

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
2. All statutory deduction will be deducted from the bill and exemption if any shall be informed with supporting documents.
3. The make of materials to be used for the work shall be from the approved make of materials mentioned in the BOQ.
4. All the works are to be carried out with good workmanship as per the latest code of practice in accordance with the rules and regulation of Kerala state Electrical inspectorate and KSEB.
5. All the work shall be completed within 20 days from the date of receipt of order.
6. The contractor shall have valid contractor and supervisor license required for the work
7. **The quotations sent through POST, envelope shall be superscribed with term QUOTATION followed by name of work.**
8. Payment Terms- 100% payment will be passed on satisfactory completion of works at site
9. The successful bidder shall execute an agreement in Kerala stamp paper with applicable Security Deposit for the fulfilment of contract. The security deposit will be released on expiry of defect liability period.

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 33 on or before **15-07-2024, 2:30 PM.**

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.

Issac Varghese
Chief Engineer

* This document is digitally approved. Hence physical signature is not required

Supply and Installation of HT metering equipment at KTDC- Hotel Nandanam, Guruvayoor

Sl No	Qty.	Specifications	Unit	Rate	Amount
1	1	Supply of 11 kV outdoor oil cooled type HT CT-PT units for metering consisting of the following components suitable for outdoor structure mounting including all necessary accessories like screws,ut, bolt frame etc complete as required at site. PT- 25 VA 11kV/110V CL 0.2 - 1 No CT 10/5A 10VA CL 0.2S - 3 Nos (Approved Make- Intrans, Indus)	set		
2	1	Installation, Testing and commissioning of outdoor CT-PT unit, HT meter in the existing DP structure including providing required channel for mounting the unit and giving connection to all power and control cables etc complete as required at site	LS		
3	1	Supply and Providing 3 phase, 4 wire, HT CT/PT operated, Uni-directional, accuracy class 0.2S for both Active and Reactive energy, -/5A, HT static tri vector meter with TOD register, DLMS compliant & AMR compatible with optical and RS232 port, having ISI Marking, suitable for measurement of active energy kWh, reactive energy kVARh and apparent energy kVAh and kVA MD, kW MD at nominal frequency in the range of 47.5Hz to 52.5 Hz in balanced as well as unbalanced load conditions in the existing metering cubicle and giving connections etc complete as required at site. The meter shall be complying to the standards prescribed by KSEB Ltd .(The meter shall be supplied with test certificate from the manufacturer)(Approved Make-L&T)	Nos		
4	1	Charges for carrying out testing new CTUnit, PT unit, HT TOD meter in the KSEB TMR including transportation, remitting testing fees, Laisoning with all required offices etc and all incidental and statutory expenses required in this regard.	LS		
5	1	Supply & Providing suitable way Test terminal Block with covering and sealing provision including giving all the control connections etc complete as required at site	Nos		

6	1	Charges for Dismantling the existing CT, PT units, old HT TOD meter, etc and its power and control connections, control cables and all related accessories required at site and hand over the same to the Maintenance department of the unit as per the directions of site in charge	LS		
7	15	Supply and laying 12C x 2.5 Sq.mm UG 2XFY PVC insulated 1.1 kV grade copper conductor control cable from CT-PT unit to HT TOD meter. (Approved make-Havells, Polycab, V Guard, RR)	m		
8	2	Supply and providing cable glanding, gland earthing and end termination of UG control cable of the size 12C x 2.5 Sq.mm with brass compression gland and copper lugs/sockets etc complete	Nos		
9	3	Supply and providing 11 kV DO fuse of good quality in the existing DP structure including dismantling of existing fuse set	Nos		
10	10	Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required 8.00 mm copper conductor (0 SWG)	m		
11	5	Supply of superior quality copper earth socket for the following size of earth conductor including crimping etc. as required 8 mm (0 SWG)	each		
TOTAL (Inclusive of GST & freight)					