



Aranya Nivas

(A unit of KTDC, Ltd Government of Kerala undertaking)
Periyar Tiger Reserve, Thekkady, MALAPPRAGAT, Kerala
Phone: (01 4888 19011) Fax: (01 4888 11128)
E-mail: aranya@ktdc.com
Web site: www.ktdc.com

KTDC/AN/EST/QN/2023-24/001

26.06.2023

QUOTATION NOTICE

Competitive quotations in sealed covers are invited from eligible licensed contractors and licensed established firm having GSTIN and PAN No for the work noted below as per the scheduled/BOC attached

Sl. No	Name of work	Time of Completion
1	Maintenance of Retaining wall at Aranya Nivas, Thekkady	45 days

General Conditions

1. The rate shall be inclusive of GST, all taxes, duties, loading and other incidental expenses and net
2. The quotationer shall visit/ inspect the site before submitting the quotation
3. The quotationer shall submit the valid licensed along with the quotation.
4. The successful quotationer shall obey the rules and regulation of forest department/ Periyar tiger reserve authority.
5. The successful quotationer will have to deposit an amount equal to 5% of the total quoted amount as security deposit and also execute agreement in stamp paper worth Rs 200/- for the due fulfillment of the contract.
6. The work should be completed as per the accompanied specification within 45 days of receipt of work order/executing agreement.

The quotation will be available from 30/06/2023 10.00 am and the offer shall reach the office of the Manager, KTDC Aranya Nivas, Thekkady on or before 10/07/2023 up to 2.30 PM & the quotation will be opened at 3.30PM on the same day.

The Management reserves the right to reject any or all quotations without assigning any reason thereof.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.

~~MANAGER~~



**BOQ OF THE WORK- Maintenance of Retaining Wall at Aranya Nivas,KTDC-Ltd,
Thekkady**

Sl No	Qty	Unit	Description	Rate	Amount
1	22.532	cum	Demolishing stone rubble masonry manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of engineer-in-charges in cement mortar		
2	3.750	cum	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to plinth level 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 normal size)		
3	33.601	Cum	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with Cement mortar 1:6 (1 cement : 6 coarse sand)		
4	13.00	cum	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with Cement mortar 1:6 (1 cement : 6 coarse sand) using departmental stone		
5	47.750	sqm	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand):Flush/ Ruled pointing		
6	18.00	cum	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil		
			TOTAL Amount Inclusive of GST		

