



KERALA TOURISM DEVELOPMENT CORPORATION LTD

(A Government of Kerala Undertaking)

Engineering Wing, Mascot Square, Thiruvananthapuram -695 033

Phone: 2318976, 2721243 Fax: ++91-471-2316168

email-ce@ktdc.com website: www.ktdc.com

AE(E)II/KTDC.EW-TVM/955/HO-TVM-HT/2019

29-07-2021

SHORT QUOTATION NOTICE

Sub: - KTDC-Corporate office, Trivandrum – Supply and Installation of new HT metering instruments - reg.

Competitive quotations are invited from reputed firms for the supply and installation of new HT metering instruments at KTDC-Corporate office, Trivandrum as per the attached schedule and following terms and conditions.

Terms & Conditions

- 1) The rate quoted shall be inclusive of GST, cost of materials, labour charges, cost of consumables, loading charges, unloading charges, insurance, other incidental expenses and net for the work at site.
- 2) No escalation of rates will be allowed under any circumstances.
- 3) All the works are to be carried out with good workmanship as per the latest code of practice in accordance with the rules and regulation of the Kerala State Electrical Inspectorate and KSEB Ltd
- 4) All the work shall be completed within **15 days** from the date of receipt of Work Order.
- 5) The Contractor shall have valid contractor and supervisor license required for carrying out the work.
- 6) The CT, PT and other instruments shall be of the make mentioned in the list of approved makes attached to this notice
- 7) Payment terms: - 100% payment will be released on full completion of all works at site.
- 8) The successful quotationer has to execute an agreement on Kerala stamp paper worth Rs.200/- with security deposit of 3% of contract amount.

The offer shall reach the office of the Chief Engineer, Kerala Tourism Development Corporation Limited, Mascot Square, Trivandrum on or before **11.00 AM, 06-08-2021**

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date / opening date.

P.K. Babu
Chief Engineer



A.E.E. (Elk)



**SUPPLY AND INSTALLATION OF NEW HT METERING INSTRUMENTS AT KTDC-
CORPORATE OFFICE, TRIVANDRUM-BOQ**

SI No	Qty	Description	Rate	Unit	Amount
1	1	Supply of 11kV Outdoor oil cooled type HT CT - PT unit for metering consisting of the following components suitable for outdoor structure mounting including all necessary accessories like clamps, screws, nuts, bolts etc. complete. PT - 25 VA, 11kV/110V, CL 0.2 - 1 No CT - 10/5A, 15VA, CL 0.2S - 3 Nos (Approved Make- Intrans, Indus Transformers or equivalent)		Nos	
2	1	Installation, Testing and commissioning of CT-PT unit in the existing DP structure and giving connection to all power and control cables etc complete as required at site		LS	
3	1	Charges for Dismantling the existing CT- PT units from HT structure etc complete as required at site		LS	
4	1	Charges for carrying out testing new CT-PT unit, HT TOD meter in the KSEB TMR including transportation, remitting testing fees, Laisoning with all required offices etc and all incidental and statutory expenses required in this regard.		LS	
5	1	Charges for carrying out testing new CTUnit, PT unit, HT TOD meter in the KSEB TMR including transportation, remitting testing fees, Laisoning with all required offices etc and all incidental and statutory expenses required in this regard.		LS	
TOTAL (Inclusive of GST)					

[Handwritten Signature]
MCC

[Handwritten Signature]
AEE (Ele)