



## Kerala Tourism Development Corporation Limited

(A Government of Kerala Undertaking)

P.B No.5424, Mascot Square, Vikas Bhavan P.O

Thiruvananthapuram –695 033, Kerala, India

Phone:++91-471- 2721243/45/48, Fax: 2721249

Website: www.ktdc.com

GST IN 32AABCK0385J1ZP

AE(E)I/KTDC.EW-TVM/113-I(iii)/HS-AC/2022

30-07-2022

### **SHORT QUOTATION NOTICE**

Sub: – KTDC – Hotel Samudra, Kovalam – Electrical works in connection with installation of split AC units in 600 block rooms and two suite rooms – Short Quotation Notice – reg.

Competitive offers are invited from eligible contractors for the Electrical works in connection with installation of split AC units in 600 block rooms and two suite rooms at KTDC Hotel Samudra, Kovalam as per the schedule attached and the following terms and conditions.

#### **Terms & Conditions**

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
2. All statutory deductions will be deducted from the bill and exemptions if any shall be informed with supporting documents.
3. The bidders shall have valid B grade contractor license with supervisor permits demanded by Kerala state Electricity Licensing Board.
4. The work shall be carried out in consultation with the KTDC officials
5. The work shall be completed within 10 days from the date of receipt of order.
6. The work has to be planned & completed without affecting the normal functioning of the Hotel.
7. All the works are to be carried out with good workmanship as per the latest code of practice in accordance with the rules and regulation of the Kerala State Electrical Inspectorate.
8. The Materials used for the work shall be from the approved make of materials mentioned in BOQ.
9. Payment Terms-100% payment will be released on full completion of all works at site.

10. The successful bidder shall execute an agreement in Kerala stamp paper worth Rs. 200/- with a Security Deposit for the fulfillment of contract. The security deposit will be released on expiry of defect liability period.

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 695 033 on or before **10-08-2022, 2:30 PM.**

**If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.**

Vigneshwari V IAS  
Managing Director

\* This document is digitally approved. Hence physical signature is not required

<b>Electrical works in connection with installation of Split AC units for 600 Block Rooms &amp; two suite rooms at KTDC-Hotel Samudra,Kovalam -Quotation BOQ</b>					
<b>Sl. No.</b>	<b>Qty.</b>	<b>Description</b>	<b>Rate</b>	<b>Unit</b>	<b>Amount</b>
		<b>Electrical works</b>			
1	350.00	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 2X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire		M	
2	14.000	Supplying and fixing 3 module GI BOX with modular plate and cover in front on surface or in recess, including providing and fixing 3/5 pin 20 A modular socket outlets with 20 A modular switch with indicator, connection etc. as required.		Each	
3	1.000	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 6 way (4+18), Double door		Each	
4	1.000	Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 amps		Each	
5	1.000	Supplying and fixing following rating, four pole, (three phase and neutral), 415 volts, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 amps		Each	
6	14.000	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole		Each	
7	4.000	Supplying and fixing single pole blanking plate in the existing MCB DB complete etc. as required.		Each	

8	15.000	Supply, laying and clamping of 1 no. PVC insulated and PVC sheathed armoured aluminium power cable, 1.1 KV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60cms, making good the damages , colour washing etc. as required. 3.5 core 25 sq mm with factory made clamp		m	
9	15.000	Supplying and laying 6 SWG G.I. wire at 0.50 metre below ground level for conductor earth electrode, including connection/ termination with GI thimble etc. as required.		m	
10	2.000	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3 1/2X25 sq.mm (28mm)		set	
		<b>TOTAL (INCLUSIVE OF GST )</b>		<b>Rs.</b>	