



# Kerala Tourism Development Corporation Limited

(A Government of Kerala Undertaking)

P.B No.5424, Mascot Square, Vikas Bhavan P.O

Thiruvananthapuram –695 033, Kerala, India

Phone:++91-471- 2721243/45/48, Fax: 2721249

Website: www.ktdc.com

GST IN 32AABCK0385J1ZP

AE(E)II/KTDC.EW-TVM/7917/HS-Kovalam-Ventilation/2023

07.08.2024

## **SHORT QUOTATION NOTICE**

Sub: - KTDC –Hotel Samudra, Kovalam- Supply, Installation, Testing and Commissioning of Fresh air, Exhaust, Hood and ducting works – Short Quotation Notice – reg.

Competitive offers are invited from eligible contractors for the Supply, Installation, Testing and Commissioning of Fresh air, Exhaust, Hood and ducting works at KTDC-Hotel Samudra, Kovalam as per the schedule attached and the following terms and conditions.

### **Terms & Conditions**

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
2. All statutory deductions including service tax will be deducted and exemption if any shall be informed with supporting documents.
3. The bidders are requested to visit the site before quoting to have a study of the site condition and nature of work.
4. The bidder shall need to submit detailed duct drawing before the commencement of work.
5. Contractor will be responsible for all the works and should submit and check all designs. The contractor should point out the changes if any, at the time of approval.
6. The work has to be planned & completed without affecting the normal functioning of the Hotel and the work should be carried out in consultation with the KTDC officials and should progress in accordance with other ongoing works if any
7. The work shall be completed within 30 days from the execution of agreement on stamp paper.

8. All the works are to be carried out with good workmanship as per the latest code of practice in accordance with the relevant standard and should depute a full time supervisor for the supervision of work
9. The bidders should give their offer in the prescribed BOQ uploaded. Offers submitted other than in the prescribed format will be liable to be rejected and has no claim even if they are the lowest.
10. The bidders should have experience in executing similar works and should attach experience certificate of one similar work whose value not less than 7 lakh or two similar works each costing not less than Rs 4 Lakhs.
11. The proof of experience must be a work completion certificate from the client. Bill, work order (Except the work done with KTDC) will not consider as work completion documents.
12. All electrical works involved shall to be in accordance with the Kerala State Electrical Inspectorate rules and regulation. Necessary approval, drawing etc are to be made by the selected contractor without any additional cost. Any modification suggested by the authorities shall be carried out at no extra cost.
13. Details of after sales service facility provided/available have to be indicated along with the offer.
14. All required documents such as as-built drawing etc are to be given at the end of satisfactory commissioning of the system.
15. The contractor has to make necessary drawing, layout, design calculations etc for approvals from the concern authorities.
16. The work shall be completed within 15 days from the date of receipt of order.
17. Payment Terms-100% payment will be released on full completion of all works at site.
18. The successful bidder shall execute an agreement in Kerala stamp paper with applicable Security Deposit for the fulfillment of contract. The security deposit will be released on expiry of defect liability period.
19. The Quotations sent through POST, envelope shall be superscripted with the term QUOTATION followed by the name of work

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 695 033 on or before **13-08-2024, 2.30 PM** & the quotation will be opened at **3.30 PM** on the same day.

**If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.**

Sikha Surendran IAS  
Managing Director

**PRESS RELEASE**

**KERALA TOURISM DEVELOPMENT CORPORATION LIMITED,  
TRIVANDRUM**

**SHORT QUOTATION NOTICE**

**NAME OF WORK: SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF FRESH AIR,  
EXHAUST, HOOD AND DUCTING WORKS AT KTDC-HOTEL SAMUDRA, KOVALAM**

Last date of receipt of offers on 13-08-2024 2.30 PM.

The quotation notice with BOQ is available in [www.ktdc.com](http://www.ktdc.com)

**Further Details can be had from:**

The Office of The Chief Engineer,  
Kerala Tourism Development Corporation Limited,  
Mascot Square,  
Trivandrum - 695 033.  
Ph-0471-2721243

**OR**

**Website: [www.ktdc.com](http://www.ktdc.com)**

Sikha Surendran IAS  
Managing Director

**SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF FRESH AIR, EXHAUST, HOOD AND DUCTING WORKS AT KTDC-HOTEL SAMUDRA, KOVALAM**

Sl No	Qty	Description	Rate	Unit	Amount
1	1	Supply, installation and commissioning of wall mounting type Exhaust Hood made of 20 swg. SS 304 sheet with detachable baffle filter and oil collection tray made of 22 swg. SS 304 sheet including all necessary structural supports required at Site. Size 1850x900x450		Nos	
2	2	Supply, installation and commissioning of wall mounting type Exhaust Hood made of 20 swg SS 304 sheet with detachable Baffle filter and oil collection tray made of 22 swg SS 304 sheet including all necessary structural supports required at Site. Size 1250x900x450		Nos	
3	1	Supply, installation and commissioning of Island type Double side Exhaust Hood made of 20 swg SS 304 sheet with detachable baffle filters and oil collection tray made of 22 swg SS 304 sheet including all necessary structural supports required at Site. Size 2100x1800x450 mm		Nos	
4	280	Supply, Installation, balancing and commissioning of fabricated at site GSS sheet metal rectangular / round ducting complete with neoprene rubber gaskets, elbows, splitter dampers, vanes, hangers, supports, etc. as per approved drawings and specifications of following sheet thickness complete as required. Site fabricated GSS sheet metal rectangular ducting as per IS 655-2006 for 0.63 mm thick		mtr	
5	125	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required. 3 X 4 sq. mm + 1 X 2.5 sq. mm earth wire		mtr	
		Wiring for circuit/ submain wiring along with earth			

6	75	wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required. 3X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire		mtr	
7	5	S & F Motor starters of the following ratings Three phase DOL starters for 0.25HP to 7.5 HP motor		Nos	
8	5	Supply and providing single phasing preventor working on 3 phase 415V AC supply		Nos	
9	3	Supply and installation of axial flow fan 1 H.P/3 phase (750 watts) for fresh air circulation. Including necessary structural support and vibration elimination connections as required.		Nos	
10	2	Supply and installation of axial flow fan 2 H.P/3 phase (1500 watts) for exhaust. Including necessary structural support and vibration elimination connections as required.		Nos	
11	1	Supplying, fixing testing commissioning of powder coated aluminum grills without volume controlled damper		sq.m	
12	280	Charges for painting outside of GSS duct using corrosion resistant FRC paint including all accessories required etc. complete.		sq.m	
<b>TOTAL (Inclusive of all taxes &amp; freight)</b>					

Sikha Surendran IAS  
Managing Director

\* This document is digitally approved. Hence physical signature is not required