

(75)



KERALA TOURISM DEVELOPMENT CORPORATION LTD

(A Government of Kerala Undertaking)

Engineering Wing, Mascot Square, Thiruvananthapuram -695 033

Phone: 2318976, 2721243 Fax: ++91-471-2316168

email-ce@ktdc.com website: www.ktdc.com

AE (E) I/KTDC.EW-TVM/283-II (A)/MH-RTR-LT/2021

24-02-2021

SHORT QUOTATION NOTICE

Sub: - KTDC-Mascot Hotel, Trivandrum – Shifting of sub panel Board and related works –
Quotation - reg.

Competitive quotations are invited from reputed firms for the shifting of sub panel Board and related works at KTDC- Mascot Hotel, Trivandrum as per the attached schedule and following terms and conditions.

Scope of work

The work includes shifting of sub panel board and laying of LT cables having the specifications as in the quotation schedule.

Terms & Conditions

- 1) The rate quoted shall be inclusive of GST, cost of materials, labour charges, cost of consumables, loading charges, unloading charges, insurance, other incidental expenses and net for the work at site.
- 2) No escalation of rates will be allowed under any circumstances.
- 3) Materials and workmanship for the entire work shall be as per the latest code of practice and standards in force at the time of supply.
- 4) All the work shall be completed within **7 days** from the date of receipt of Work Order.
- 5) **The Contractor shall have valid B grade contractor license with valid B grade supervisor permit with minimum scope of All LT/ MV electrical installation, issued by Kerala state Electricity Licensing Board. The firm shall have to submit experience certificate of two similar works costing not less than Rs. 1 Lakhs in the last three years.**
- 6) All Electrical installation / materials used shall be in accordance with the existing rules and regulations of the Electrical Inspectorate.
- 7) The quantities given in the BOQ may vary as per the site requirement. The payment will be made to the actual quantities of materials used based on unit rates.
- 8) Necessary testing shall be carried out by the contractor after completion of the work without any additional cost.
- 9) Payment terms: - 100% payment will be released on full completion of all works at site.
- 10) **The quotations shall be enclosed and submitted in a sealed envelope on which the name of work shall be clearly superscribed. Otherwise the quotations will be summarily rejected.**



Handwritten signature and date:
25/2/2021
CB/AM

177

The offer shall reach the office of the Chief Engineer, Kerala Tourism Development Corporation Limited, Mascot Square, Trivandrum on or before **11.00 AM, 01/03/2021** superscribing the name of the work on the cover.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date / opening date.


P.K. Babu

Chief Engineer



AEE(CE)



179

**SHIFTING OF SUB PANEL BOARD AND RELATED WORKS AT MASCOT HOTEL,
TRIVANDRUM - QUOTATION- BOQ**

Sl No	Qty.	Description	Unit	Rate	Amount
SHIFTING OF SUB PANEL BOARD					
1	50	Supply & laying of one No. PVC insulated and PVC sheathed armoured aluminium power cable of 1.1 KV grade of the following sizes in the existing masonry open duct as required.3.5 core 70 sq mm	Mtr		
2	25	Supply & laying of 4C x 2.5 sq mm armoured copper cable of 1.1 KV grade of following size cable through trench/wall/ ceiling including end termination etc . complete.	Mtr		
3	10	Supply & laying of one No. PVC insulated and PVC sheathed armoured aluminium power cable of 1.1 KV grade of the following sizes in the existing masonry open duct as required.3.5 core 25 sq mm	Mtr		
4	25	Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required4.00 mm copper conductor (8 SWG)	Mtr		
5	10	Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required4.75 mm copper conductor (6 SWG)	Mtr		
6	50	Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required6.00 mm copper conductor (4 SWG)	Mtr		
7	2	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.3 1/2X 70 sq mm (38 mm)	set		
8	4	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.3 1/2X25 sq.mm (28mm)	set		
9	2	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.31/2 X 25 sq. mm	each		



Handwritten signature and initials in blue ink.

10	1	Dismantling and repositioning of existing sub panel board having 125A MCCB as incomer & 6 MCCBs as outgoing to the next floor level including removing existing cable trays, incomer and outgoing cables etc. complete.	LS		
11	1	Dismantling the existing DB, related wires/cables, PVC conduits etc completely from the wall including stacking the materials and hand over the same to the unit	Day		
12	25	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Upto 35 sq. mm (clamped with 1mm thick saddle)	Mtr		
13	4	Painting of existing panel board (size 2mx0.9m) with one or more coat of synthetic enamel paint of approved brand and manufacturer of required colour and labeling incoming and outgoing cables as per standard etc. complete.	sq.m.		
TOTAL (Inclusive of all taxes)				Rs.	



P K BABU
Chief Engineer



AEE(E2)

