



**KERALA TOURISM DEVELOPMENT CORPORATION LIMITED**

(A Government of Kerala Undertaking)

Engineering Wing, Mascot Square, Thiruvananthapuram -695 033

Phone: 2318976, 2721243 Fax: ++91-471-2316168

[email-chiefengineer@ktdc.com](mailto:email-chiefengineer@ktdc.com) website: [www.ktdc.com](http://www.ktdc.com)

KTDC/EW/ELE/ANH/HT/04/2019

03-05-2019

**QUOTATION NOTICE**

Sub:- KTDC-Aranya Nivas Hotel, Thekkady –Transformer Oil filtration & related works -reg.

Competitive quotations are invited from reputed firms for the Transformer Oil filtration & related works at KTDC-Aranya Nivas Hotel, Thekkady as per the attached schedules and terms & conditions given below.

**Terms & Conditions**

1. The rate shall be inclusive of all taxes, duties, loading and unloading charges, transportation, other incidental expenses and net for the work at site.
2. The work shall be completed within 20 days from the date of receipt of work order.
3. All the works are to be carried out with good workmanship as per the latest code of practice in accordance with the rules and regulation of the Electrical Inspectorate.
4. The Existing Transformer Oil has to be filtered with the associated Equipments and it must be ensured with the Engineer in charge, that the final filtered Oil has the BDV value and acidity parameters conforming to the Electrical Inspectorate standards/ IS6792-1992/IS 1866-2000.
5. Payments Terms-100% payment will be released on satisfactory completion of all works in all aspect.


The offer shall reach the office of the Chief Engineer, Kerala Tourism Development Corporation Limited, Mascot Square, Trivandrum on or before **2.30 PM, 17-05-2019** super scribing the name of the work on the cover.

**If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date / opening date.**

  
EXECUTIVE ENGINEER (CIVIL)

**TRANSFORMER OIL FILTRATION AND RELATED WORKS AT KTDC- ARANYA  
NIVAS HOTEL, THEKKADY**

SI No	Qty	Description	Rate	Unit	Amount
1	275	Charges for carrying out Oil Filtration of the 1 No of existing 3 Phase, 200 KVA, 11000/433V KEL make Transformer at site. ( To restore the BDV to a minimum value of 40kV) confirming to IS 6792 -1992 / IS 1866-2000		Ltr	
2	30	Supply of fresh Transformer Oil of suitable break down strength, grade and of best quality as top up for the losses.		Ltr	
3	1	Charges for the transportation of oil filtering equipments and the related accessories to the site and back .		LS	
4	1	Charges for conducting Transformer Oil BDV & acidity test and issuing test certificate as per Electrical inspectorate standards.		LS	
<b>TOTAL (Inclusive of all taxes)</b>					



Handwritten signatures and initials, including a large signature on the left and a smaller one with a horizontal line through it on the right.