



AE(E)II/KTDC.EW-TVM/601/HO-TVM-AC/2019

21-10-2020

Quotation Notice



Sub: - KTDC-Corporate office, Trivandrum – Supply, installation, testing and commissioning of ductable Split type air conditioner in Chairman's Office – reg.


Competitive offers are invited from eligible and reputed firms for the Supply, installation, testing and commissioning of 5.5 TR capacity ductable split type air conditioning units in the Chairman's office at KTDC-Corporate Office, Trivandrum as per the schedule attached and the following terms and conditions.

Terms & Conditions

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
2. All statutory deduction will be deducted from the bill and exemption if any shall be informed with supporting documents.
3. The makes of AC units shall be from the approved makes mentioned in the BOQ
4. The offer shall be valid for 30 days from the last date of submission of offers.
5. The work shall be carried within 15 days from the date of work order.
6. The warranty period of the supplied items should be a **minimum of 1 year** from the date of testing and commissioning and the actual warranty period of AC, PC Board, compressor and etc shall be clearly indicated in the offer.
7. The leaflet bearing the complete technical specifications of the product shall be enclosed along with the offer.
8. Payment Terms- 100% payment will be passed on satisfactory supply, Installation, testing and commissioning of equipments at site.
9. The successful bidder shall execute an agreement in Kerala stamp paper worth Rs. 200/- with a Security Deposit of 5% of contract value for the fulfillment of contract. The security deposit will be released on expiry of defect liability period

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 33 on or before **05-11-2020, 2.30 PM.**

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.


P.K Babu
CHIEF ENGINEER



7

SUPPLY, INSTALLATION, TESTING AND COMMISSIONING DUCTABLE TYPE SPLIT AIR CONDITIONING UNITS IN CHAIRMAN'S OFFICE AT KTDC-CORPORATE OFFICE, TRIVANDRUM-BOQ

Sl. No.	Qty	Description	Rate	Unit	Amount
1	1	Supply, Transportation, leading, lifting to site of 5.5 TR capacity air cooled ductable split air conditioner working on three phase 415V 50 Hz AC supply with scroll compressor, full copper evaporator and condensor coils, microprocessor control box, including best quality canvas connection for connecting indoor units to the air supply ducts, full charge of refrigerant gas as per OEM standards, wireless remotes, necessary ribbed rubber pads etc complete as required at site		set	
2	1	Installation, Testing and Commissioning of above said ductable split AC units (Both indoor and outdoor) including fixing, full charge of refrigerant gas, leak testing/pressure testing, giving all power/control/refrigerant connections etc and all required works as per prevailing code of standards.		Set	
3	10	Supply & laying suction refrigerant lines using hard drawn copper pipe of the adequate size recommended by the manufacturer for above mentioned AC unit including duly insulated with nitrile rubber thermal insulation of recommended capacity and all other materials required as per prevailing standards, clamping to wall, supports required etc complete as required at site. The exposed portion in outer area shall be covered with weather proof coating as per standards. PVC sleeves shall be provided in the wall opening for the protection of refrigerant and control circuits and these opening shall be sealed properly		RM	

[Handwritten signature]
A/c

[Handwritten signature]
Chief Engineer
21/10/2017