

QUOTATION NOTICE

Sub: KTDC –Structural frame work for vertical garden at Motel Araam, Vaikom- reg.


Competitive quotations are invited from eligible licensed contractors for Structural frame work for vertical garden as specified below.

Sl. No	Qty	Unit	Description	Rate	Amount (Rs)
1	340.201	kg	Steel work in built up G I tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete		
2	55.5	sqm	Providing and fixing G.P 50x50 mm mesh of wire diameter 5 mm to steel frames etc. all complete		
3	2.592	cum	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil		
4	2.592	cum	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)		
5	72.061	sqm	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work		
			TOTAL		

The rate shall be inclusive of all taxes, duties, loading and other incidental expenses and net.

The offer in sealed cover shall reach the office of the Manager, Regional Office (Central), KTDC Ltd, Mattoor – Kaipattoor Road, Kalady, Ernakulam District – 683574 on or before 29/04/2021 up to 2 pm & the quotation will be opened at 2.30 pm on the same day.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.


Manager
Regional Office (Central)



QUOTATION FORM

Sub: KTDC –Structural frame work for vertical garden at Motel Araam, Vaikom- reg.

Sl. No	Qty	Unit	Description	Rate	Amount (Rs)
1	340.201	kg	Steel work in built up G I tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete		
2	55.5	sqm	Providing and fixing G.P 50x50 mm mesh of wire diameter 5 mm to steel frames etc. all complete		
3	2.592	cum	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil		
4	2.592	cum	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)		
5	72.061	sqm	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work		
			TOTAL		

Name, Address & Mobile no. of the tenderer

GST No:

PAN :

Signature
Name

(Copy of Address proof, GST proof, PAN card to be attached)

