



KERALA TOURISM DEVELOPMENT CORPORATION LIMITED

(A Government of Kerala Undertaking)

Engineering Wing, Mascot Square, Thiruvananthapuram -695 033

Phone: 2318976, 2721243 Fax: ++91-471-2316168

Email: chiefengineer@ktdc.com website: www.ktdc.com

EE(C)/KTDC.EW-TVM/1207/R&M_HO/2019

06-03-2020

QUOTATION NOTICE

Sub:- Construction of Roof changing work at store room (2nd floor) KTDC Corporate Office, Trivandrum – reg;

Competitive quotations are invited from reputed firms having similar experience for the **Construction of Roof changing work at store room (2nd floor), KTDC Corporate Office, Trivandrum** as specified below.

Sl No	Qty	Description	Unit	Rate	Amount
1	15	Dismantling roofing including ridges, hips, velleys and gutters etc., and stacking the material within 50 metres lead of :G.S. Sheet	sqm		
2	15	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead.	sqm		
3	5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: One or more coats on old work.	sqm		
4	5	Applying priming coat: With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron /steel works	sqm		
5	15	Supplying and laying Trafford profile sheet having 750-780mm cover width with 26/28mm high crest at 190/200mm centres with a rib between two crest made out of 0.5mm or nearest TCT, minimum 300MPa yield strength cold rolled steel with hot dipmetallic coating of Aluminium zinc alloy (Galvalume) 150gms/sqm, total of both sides ,AZ 150 as per ASTM A 792 or AS 1397, with polyester colour coating ,in length upto 6m to suit requirements, over the roof truss with over lap of 150 mm, including ridge capping, valleys etc, fixed with j bolts, nuts, Fan clamps ,bitumen washers, GI washers, repositing existing steel members wherever necessary, including cost of materials, labour charges etc. completed as per the direction of engineer in charge.(JSIS/TATA) or equivalent. The sheet should be provided 2 cm inside the wall after raking/recessing the wall at the junction and curbing using cement mortar 1:3 including apply of one layer silicon sealant	sqm		

o	15	Refixing false ceiling using glazed/matt-finish PVC boards (8mm thick)already erected from the room using supporting sections, screws, etc. including all labour charges	sqm		
7	10	Plastering the edges of the roofing sheet with cm 1:3 with waterproofing compound of approved brand after dismantling the existing plaster including all labour charges as per the direction of engineer in chage	m		
8	8	Supplying and providing false ceiling using glazed/matt-finish PVC boards (8mm thick or nearest) of good quality suspended from bottom of RCC slab using supporting sections, screws, etc. including all material cost, labour charges, conveyance etc. Complete. (charges inclusive of providing holes for light fittings)	sqm		
		TOTAL			

The rate shall be inclusive of all taxes, duties, loading and other incidental expenses and net.

The offer shall reach the office of the Chief Engineer, Kerala Tourism Development Corporation Limited, Mascot Square, Trivandrum – 33 on or before **12-03-2020 up to 2.30 PM** & the quotation will be opened at **3.30PM** on the same day.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.


EXECUTIVE ENGINEER (CIVIL)



