

QUOTATION NOTICE

KTDC /RBP Pullurampara/2024

DATE 28-09-24

Sub: KTDC – Premium Beer Parlour at the RBP Pullurampara– reg-

Competitive quotations are invited from PWD/CPWD/Public Sector registered eligible licensed contractors for the Premium Beer Parlor at the RBP Pullurampara as per the schedule of work attached herewith.

The rate shall be inclusive of all taxes, duties, loading, and other incidental expenses and net. A copy of the license, PAN, GST proof and Address proof are to be attached.

The offer with name, address, signature and mobile number of the tenderer in sealed cover shall reach the Manager, Restaurant and Beer Parlour, KTDC Ltd, Pullurampara, Kozhikode, 673603 on or before 10/10/2024 up to 2 pm & the quotation will be opened at 2.30 pm on the same day.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.

Manager
Restaurant and Beer Parlour
KTDC Ltd., Pullurampara

SL.NO	QTY	UNIT	DESCRIPTION	RATE	AMOUNT (Rs)
1.	27.36	sqm	<p>Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/ sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37 mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50 mm long with 6 mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25 mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5x25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with:12.5 mm thick tapered edge gypsum plain board conforming to IS : 2095-Part 1</p>		
2.	27.36	Sqm	<p>Applying one coat of water-thinnable cement primer of approved brand and manufacture on wall surface: Water-thinnable cement primer</p>		

3.	27.36	Sqm	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work		
4.	12.60	Sqm	Providing and fixing cabin partition 10 cm overall thickness with 12 mm thick marine plywood box conforming IS: 710 and 1.0 mm thick decorative laminated sheet fixed on both sides with all edges bent finish. Accessories using hectic or sleek. Includes all labor, material and transportation cost etc. complete		
5.	7.00	Each	Supplying and providing three seater sofa made of 12 mm plywood as per the direction of the Engineer in charge and cushion for seating and back made of in 3"elastic form with rexine sheet of approved colour , design as per direction of Engineering in Charge		
6.	3.00	Each	Supply of 6 seater granite top dining table with frame made of metal with painting. The rate includes all labour, material and transporation cost etc. complete.		
7.	27.36	Sqm	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.		
8.	34.40	m	Gypsum Step Ceiling:Providing and fixing Gypsum Step ceiling with width/ depth less than or equal to 150 mm as per approved design.Frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both Side inclusive) as per IS : 277 ,ie,perimeter channels 0.5 mm thick 27 mm high having flanges of 20 and 30 mm long to be fixed as per design intent and 12.5 mm thick Moisture Resistant Gypsum board to be fixed on to the framework using 25 mm long dryWall screw.Finish the joints using jointing compound and joint tap as per manufacture specification.Including cost and conveyance of all materials labour charges etc.complete as per direction of Engineer-in-charge. The visible Vertical Sides will be measured in meter		

9.	61.80	Sqm	Finishing walls with Acrylic Smooth exterior paint of required shade :Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cementpaint surface		
----	-------	-----	--	--	--

Name and full address of the applicant

with mobile number, email address & GST Number

Date :

Place :

Signature with Seal