



Lake Palaces

(A unit of KTDC Ltd-Government of Kerala undertaking)
Periyar Tiger Reserve, Thekkady, Idukki-685536, Kerala
Phone +91-4868-250111 Fax: +91- 04869-222282
E-mail:lakepalaceoffice@gmail.com
Web site: www.ktdc.com

KTDC/LP/EST/QN/2024-25/771

17.07.2024

QUOTATION NOTICE

Competitive quotations in sealed covers are invited from eligible licensed contractors and licensed established firm having GSTIN and PAN No. for the work noted below as per the scheduled/BOQ attached.

SL No	Name of work	Time of Completion
1	Providing of Roof and Grill door at Lake palace, Thekkady	3 months

General Conditions

1. The rate shall be inclusive of GST, all taxes, duties, loading, unloading and other incidental expenses and net.
2. The bidder shall visit/ inspect the site before submitting the quotation.
3. The bidder shall submit the valid licensed along with the quotation.
4. The successful bidder shall obey the rules and regulation of forest department/ Periyar tiger reserve authority.
5. The successful bidder will have to deposit an amount equal to 5% of the total quoted amount as security deposit and also execute agreement in stamp paper worth Rs.200/- for the due fulfillment of the contract.
6. The successful bidder shall obtain approvals for the materials and detail of proposed work from the engineering officials of KTDC.
7. The work should be completed as per the accompanied specification within **3 months** of receipt of work order/executing agreement.

The quotation will be available from **19/07/2024 10.00 am** and the offer shall reach the office of the Manager, KTDC Lake palace, Thekkady on or before **30/07/2024 up to 2.30 PM** & the quotation will be opened **at 3.30PM** on the same day.

The Management reserves the right to reject any or all quotations without assigning any reason thereof.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.

MANAGER



BOQ OF THE WORK- providing roof and grill door at Lake Palace,KTDC-Ltd, Thekkady

Sl No	Qty	Unit	Description	Rate with tax	Amount
1	107.45kg	kg	10.25.2 : Item Shifted to head 14 as item 14.74Steel work welded in built up sections/framed work, Including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works		
2	7	m	od307056/2023_2024 : Supplying and fitting 200mm square uPVC rainwater gutter pipe with fittings
32mmx5mm MS Flat supports at 1m interval
		
3	135	kg	10.16.1 : Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes		
4	45	M2	od352366/2023_2024 : Providing & fixing Polycarbonate solid sheet 6 mm thick as approved by the Engineer in charge and should be supplied in a single length of 12m or as decide by the Engineer in charge. The sheets shall be fixed using self drilling/self tapping screw of size (5.5x55mm) with EPDM seal complete upto any pitch in horizontal/vertical curved surfaces, but excluding the cost of purlins, rafters, trusses, and including cutting to size and shapes where ever required.		
			TOTAL Amount Inclusive of GST		

