



Kerala Tourism Development Corporation Limited

(A Government of Kerala Undertaking)
P.B No.5424, Mascot Square, Vikas Bhavan P.O,
Thiruvananthapuram –695 033, Kerala, India
Phone: ++91-471- 2721243/45/48, Fax: 2721249
E-mail: it@ktdc.com website: www.ktdc.com
GST IN: 32AABCK0385J1ZP

KTDC/ITD/HC/01

18.11.2020

QUOTATION NOTICE

Sub:- Supply and Installation of Network cables and CCTV Surveillance System at Hotel Chaithram- reg.


Sealed quotations are invited from experienced and reputed firms for the supply and installation of Network cables and CCTV Surveillance System at Hotel Chaithram, Thiruvananthapuram as per the attached schedule and the following terms & conditions.

Terms & conditions

1. The rate shall be inclusive of all taxes, duties, loading and unloading charges, transportation, other incidental expenses and net for the work at above sites.
2. The payment will be as per the actual measurement of quantities deployed at site and the quantities mentioned in the schedule are tentative and may vary as per the site conditions.
3. Payment will be released after the satisfactory supply, installation, testing and commissioning of CCTV Surveillance and Network System keeping 5% as retention for the defect liability/warranty period.
4. The CCTV items supplied should have a warranty for a minimum period of 2 years and Network system for a period of 1 year. Any service requirement needed within the warranty period has to be attended at the site.
5. The firm shall have GST registration for work contract and proof of same shall be provided along with the offer.
6. The work shall be carried out in consultation with the Unit Manager without affecting the routine operation of the unit.
7. The materials used for the work should be from the attached approved list of make of materials.
8. Security deposit of 5% of the contract amount should be remitted before starting the work.

The offer containing the signed copy of the quotation notice along with the filled in price format shall reach the office of the System Analyst, KTDC Ltd., Mascot Square, Trivandrum – 695 033 on or before 23.11.2020, 3 P.M. and will be opened on 23.11.2020 4 PM. Further details if required can be had from the office of the System Analyst, KTDC Ltd., Thiruvananthapuram.

If the last date mentioned falls as a holiday or hartal, the very next working day will be treated as the last date.


SYSTEM ANALYST

Schedule I for Network System Installation Works at Hotel Chaithram

Part-A

SI No	Description	Qty	Unit	Unit Rate	Subtotal	Tax %	Tax Amount	Grand Total
1	Supply of CAT-6 Network Cable.	225	Mtr.					
1.1	Supply of 4U Rack fully loaded.	1	Mtr.					
1.2	Supply of 16 Port Gigabyte Unmanageble Network switch.(Rack Mountable)	2	Nos.					
1.3	Supply of Network IO Box and Connectors.	5	No.					
1.4	Supply of 20mm & 25mm PVC conduits/casing capping, (Standard ISI medium) with all accessories such as saddles etc and complete.	150	Mtr.					
Total A								

Part-B

2	Installation charges for above location (Labour Charges)							
2.1	Laying charge for CAT-6 Network Cable.	225	Mtr.					
2.2	Installation charge for 6U Rack fully loaded.	1	No.					
2.3	Installation charge for 16 Port Gigabyte Unmanageble Network switch.(Rack Mountable)	2	No.					
2.4	Supply and Installation of RJ 45 Connectors.	16	No.					
2.5	Laying charge for 20mm & 25mm PVC conduits/casing capping, (Standard ISI medium) with all accessories such as saddles etc and complete.	150	Mtr.					
2.6	Installation charge for Network IO Box and Connectors.(concealed)	5	No.					
2.7	Charges for Installation, testing and commissioning the entire Network System.	1	Mtr.					
Total B								
Total (Part-A+B)								

Schedule II for CCTV Surveillance System Installation Works at Hotel Chaithram

SI No	Description	Qty	Unit	Unit Rate	Sub total	Tax %	Tax Amt	Grand Total
1	Supply of Indoor 2 Megapixel High Definition Dome Camera of good quality & approved make with 1080P resolution, 3.6mm lens, minimum 20 meters IR range, day/night vision, Weather Resistant IP 66 housing, RoHS Compliance etc complete.	6	Nos.					
2	Supply of BNC Connectors.	12	Nos.					
3	Supply of DC Pin Connectors.	6	Nos.					
4	RG-6 CO-Axial cable and 2 Pair Standard 1 sqmm Copper Power Cable through conduit including of wall if necessary etc and complete.	475	m.					
5	Supply of 25mm PVC conduits/casing capping, (Standard ISI medium) 8 no 4×4 pvc Box with all accessories such as saddles etc and complete.	250	m.					
	Total A							
	Part-B							
2	Installation charges for above location (Labour Charges)							
2.1	Laying Charges for RG-6 CO-Axial cable and 2 Pair Standard 1 sqmm Copper Power Cable through conduit including of wall if necessary etc and complete.	475	m.					
2.2	Laying Charges for 25mm PVC conduits/casing capping, (Standard ISI medium) 8 no 4×4 pvc Box with all accessories such as saddles etc and complete.	250	m.					
2.3	Charges for Installation, testing and commissioning the entire CCTV Surveillance System.	1	Ls.					
	Total B							
	Total (Part-A+B)							
	Grand Total (Schedule I + Schedule II)							

LIST OF APPROVED MAKES OF MATERIALS

SI No.	Material	Makes
1	16 port Gigabyte Unmanageable Network Switch (Rack mountable)	Cisco / D-Link / HP
2	CAT 6A cable	D-Link / Finolex/V-Guard
3	6U Network Rack	D-Link/ Rittal / Mass
4	I/O Box	D-Link/Finolex/V-Guard
5	Camera.	Hikvision, Sony, Samsung,Panasonic..
6	BNC Connectors.	MX.
7	DC Pin connectors.	MX
8	Coaxial cable.	Finolex/ V-Guard.