



Kerala Tourism Development Corporation Limited

(A Government of Kerala Undertaking)

P.B No.5424, Mascot Square, Vikas Bhavan P.O

Thiruvananthapuram –695 033, Kerala, India

Phone:++91-471- 2721243/45/48, Fax: 2721249

Website: www.ktdc.com

GST IN 32AABCK0385J1ZP

AE(E)II/KTDC.EW-TVM/500/TEH/Neyyar Sanctuary/LT/2022

09-12-2022

QUOTATION NOTICE

Sub: - KTDC – Tamarind Easy Hotel, Neyyar Dam – Supply and providing light fittings in Beer Parlour – Quotation Notice – reg.

Competitive offers are invited from eligible contractors for the supply and providing light fittings in Beer Parlour at KTDC- Tamarind Easy Hotel, Neyyar Dam as per the schedule attached and the following terms and conditions.

Terms & Conditions

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
 2. All statutory deductions will be deducted from the bill and exemptions if any shall be informed with supporting documents.
 3. The bidders shall have valid contractor license with supervisor permits demanded by Kerala state Electricity Licensing Board.
 4. The work shall be carried out in consultation with the KTDC officials
 5. The work shall be completed within 20 days from the date of receipt of order.
 6. The work has to be planned & completed without affecting the normal functioning of the Hotel.
 7. All the works are to be carried out with good workmanship as per the latest code of practice in accordance with the rules and regulation of the Kerala State Electrical Inspectorate.
 8. The Materials used for the work shall be from the approved make of materials mentioned in BOQ.
 9. **For quotations sent through POST, the envelope shall be superscribed with the term QUOTATION followed by name of work.**
 10. Payment Terms:- 100% payment will be released on full completion of all works at site.
-

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 695 033 on or before **19-12-2022, 2.30 PM.**

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.

Issac Varghese
Chief Engineer

* This document is digitally approved. Hence physical signature is not required

**Schedule for supply and providing Light fittings in Beer Parlour at Tamarind Easy Hotel,
Neyyar Dam**

| Sl. No. | Qty | Description | Rate | Unit | Amount |
|---------|-----|---|------|------|--------|
| 1 | 38 | Supply, installation, testing & commissioning of 6 W Round /Square concealed ceiling LED fittings including all the accessories like clamps,screws and standard length connection leads etc. required for fixing and working on 240 V, 50 Hz AC supply. | | Nos. | |
| 2 | 5 | Supply, conveyance, installation, testing and commissioning of recess mounting 12 watts concealed ceiling LED down lights including all the accessories etc.complete required for fixing and working on 240 V, 50 Hz AC supply | | Nos. | |
| 3 | 2 | Supplying and fixing polycarbonate angle holder including connection etc. as required. | | Nos. | |
| 4 | 2 | Supply of 9W B22 LED lamp | | Nos. | |
| 5 | 3 | Supply. conveyance, installation, testing and commissioning of 200 mm light duty exhaust fan working on 230 V single phase A/C of good quality & approved make to the existing openings/false ceiling including making good damages with 3Cx1.5 sq.mm. FR PVC insulated copper conductor, flexible cable etc as required | | Nos. | |
| 6 | 1 | Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit,with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required. Group A | | No. | |
| | | Supply. conveyance, installation, testing and commissioning of 450 mm Heavy duty exhaust fan working on 230 V single phase A/C of good | | | |

| | | | | | |
|---|---|--|--|------|--|
| 7 | 1 | quality & approved make to the existing openings/false ceiling including making good damages with 3Cx1.5 sq.mm. FR PVC insulated copper conductor, flexible cable etc as required. | | No. | |
| 8 | 7 | Charges for fixing the LED Hanging light fittings in the ceiling and giving connection etc complete as required at site. | | Nos. | |
| | | TOTAL(inclusive of GST and freight) | | ₹ | |

Issac Varghese
Chief Engineer

| LIST OF APPROVED MAKES OF MATERIALS FOR ELECTRICAL WORKS | | |
|--|--------------------------------------|--|
| Sl. No. | Material | Make |
| 1 | Modular Switches | Legrand, MK, L&T |
| 2 | PVC copper wires | Finolex, Havells, V Guard, RR Kabel, Polycab |
| 3 | Distribution boards (IP 43) | Legrand, Schneider, Siemens, Hager, Indoasian |
| 4 | ELCB /MCB/RCCB/ RCBO/MCB COS/MPCB | Legrand, Schneider, Siemens, Hager, Indoasian |
| 5 | LT Cables | Gloster, Nicco, Havells, Finolex, RR, Polycab |
| 6 | LT Cable glands | Commex, Dowels |
| 7 | PVC Conduits | Avon plast, Balco, Circle arc, Precision |
| 8 | Casing/ Capping | Modi, Precision or equivalent approved |
| 9 | SDFU / SFU / TPN Isolators | L&T, Siemens, Schneider |
| 10 | Light fittings | Philips, Crompton, Havells, Wipro, Luker |
| 11 | Lamps | Philips, Osram, Crompton Greeves, Wipro, Luker |
| 12 | Junction Boxes | Hensel, Cape Electric, Sintex |
| 13 | Exhaust fan | Usha, Havells, Bajaj, Almonard, Crompton |

Issac Varghese
Chief Engineer