



## Kerala Tourism Development Corporation Limited

(A Government of Kerala Undertaking)  
P.B No.5424, Mascot Square, Vikas Bhavan P.O,  
Thiruvananthapuram –695 033, Kerala, India  
Phone:++91-471- 2721243/45/48, Fax: 2721249  
E-mail: [it@ktdc.com](mailto:it@ktdc.com) website: [www.ktdc.com](http://www.ktdc.com)  
GST IN: 32AABCK0385J1ZP

KTDC/ITD/TEH-T/Wi-Fi/01

10.02.2025

### QUOTATION NOTICE

Sub:- Supply and Installation of Wi-Fi Access Points and LAN at KTDC Tamarind Easy Hotel,  
Thirunelly- reg.

Sealed quotations are invited from experienced and reputed firms for the supply and installation of Wi-Fi Access Points and LAN at KTDC Tamarind Easy Hotel, Thirunelly as per the attached schedule and the following terms & conditions.

#### Terms & conditions

1. The rate shall be inclusive of all taxes, duties, loading and unloading charges, transportation, other incidental expenses and net for the work at above sites.
2. The payment will be as per the actual measurement of quantities deployed at site and the quantities mentioned in the schedule are tentative and may vary as per the site conditions.
3. Payment will be released after the satisfactory supply, installation, testing and commissioning of Network System keeping 5% as retention for the defect liability/warranty period.
4. The Wi-Fi accessories supplied should have a warranty for a minimum period of 1 year. Any service requirement needed within the warranty period has to be attended at the site.
5. The firm shall have GST registration for work contract and proof of same shall be provided along with the offer.
6. The work shall be carried out in consultation with the Unit Manager without affecting the routine operation of the unit.
7. The materials used for the work should be from the attached approved list of make of materials.
8. Security deposit of 5% of the contract amount should be remitted before starting the work.
9. The payment will be released within 30 days on satisfactory supply and installation of the items at site.

The offer containing the signed copy of the quotation notice along with the filled in price format shall reach the office of the System Analyst, KTDC Ltd., Mascot Square, Trivandrum – 695 033 on or before **20.02.2025 - 2.30 PM**. Further details if required can be had from the office of the System Analyst, KTDC Ltd., Thiruvananthapuram

If the last date mentioned falls as a holiday or hartal, the very next working day will be treated as the last date.

**SYSTEM ANALYST**

**SCHEDULE FOR WI-FI SYSTEM INSTALLATION WORKS AT KTDC TAMARIND.****THIRUNELLY****Part-A**

Sl No	Description	Qty	Unit	Unit Rate	Sub total	Tax Amt	Grand Total	
1	Supply and installation of <b>Guest Wi-Fi Management Device/ Router for 50 concurrent users</b>	1	No.					
2	Supply and installation of Ceiling Mount/Wall Mount Wi-Fi Access Point (Dual Band) with PoE adaptor	4	Nos.					
3	Supply and installation of 8 Port Gigabit PoE Ethernet Switch	1	No.					
4	Supply and Installation of 6U Rack Fully Loaded with all accessories. (Rack Tray, Surge Protector)	1	No.					
5	Supply and Installation of 16 Port Patch Panel with all accessories.	1	No.					
6	Supply and Installation RJ 45 Connectors.	20	Nos.					
7	Supply of 1Mtr Patch Cord.	10	Nos.					
8	Supply of CAT 6 Network cable.	350	Mtr					
9	Supply of 25mm PVC conduits/casing capping, (Standard ISI medium) with all accessories such as saddles etc and complete.	200	Mtr					
10	Supply of 25mm PVC Water pipe (Standard ISI ) with all accessories such as saddles etc and complete.	50	Mtr					
11	Supply of 1KVA Offline UPS	1	No.					
	<b>Total A</b>							
<b>Part-B</b>								
12	Laying Charges for CAT-6 Network Cable through conduit including of wall if necessary etc and complete.	350	Mtr					
13	Laying Charges for 25mm PVC conduits/casing capping with all accessories such as saddles etc and complete.	200	Mtr					
14	Laying Charges for 25mm pvc Water pipe(Standard ISI ) with necessary Digging, fittings & accessories such as saddles etc and complete.	50	Mtr					
	<b>Total B</b>							
	<b>Grand Total (Part-A+B)</b>							

**LIST OF APPROVED MAKES OF MATERIALS**

<b>SI No.</b>	<b>Material</b>	<b>Makes</b>
1	Guest Wi-Fi Management Device/ Router for 50 concurrent users	TP Link OC 200 Omada Hardware Controller
2	Ceiling/Wall Mount Wi-Fi Access Point ( Dual Band )	TP-Link/ Mikrotik/ Ubiquiti
3	8 Port Gigabit PoE Ethernet Switch	TP-Link/ D-Link / Cisco
4	16 Port Patch Panel	TP-Link/ D-Link/ Molex
5	RJ 45 connector	D-Link/ Molex
6	CAT6A Cable	D- Link/ Molex/ Finolex
7	6U Network Rack	D-Link/ Rittal/Mass
8	PVC Conduit/Pipe	Standard ISI medium
9	Water Pipe	Standard ISI medium
10	1Mtr Patch Cord	D-Link/ Amp/ Legrand
11	1KVA Offline UPS	Numeric/ APC/ V-Guard/ Hykon