



Kerala Tourism Development Corporation Limited

(A Government of Kerala Undertaking)

P.B No.5424, Mascot Square, Vikas Bhavan P.O

Thiruvananthapuram –695 033, Kerala, India

Phone:++91-471- 2721243/45/48, Fax: 2721249

Website: www.ktdc.com

GST IN 32AABCK0385J1ZP

AE(E)II/KTDC.EW-TVM/4488/Aahar-Mannarkkadu-DG set/2024 (IX)

24.09.2024

Quotation Notice

Sub: - KTDC – Aahaar Restaurant, Mannarkkad – Installation of 40 kVA DG set – reg.

Competitive offers are invited from eligible and reputed firms for the Installation of supplied 40 kVA DG set at KTDC – Aahaar Restaurant, Mannarkkad as per the schedule attached and the following terms and conditions.

Sl. No.	Name of work	Time of completion	Eligibility
1	Installation of supplied 40 kVA DG set at KTDC – Aahar Restaurant, Mannarkkad	20 days	Eligible contractors with required scope and those who have executed the installation of same or higher capacity DG sets in past three years. Proof of valid contract license and supervisor permit and details of experience shall be submitted along with offer.

Terms & Conditions

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
2. All statutory deduction will be deducted from the bill and exemption if any shall be informed with supporting documents.
3. The bidders shall have valid license and required scope demanded by Kerala state Electricity Licensing Board.
4. The work shall be carried out in consultation with the KTDC officials
5. The work has to be planned & completed without affecting the normal functioning of the Hotel

6. The make of materials used for the work shall be from the approved make of materials mentioned in the BOQ.
7. All the works are to be carried out with good workmanship as per the latest code of practice in accordance with the rules and regulation of Kerala state Electrical inspectorate.
8. **The quotations sent through POST, envelope shall be superscribed with term QUOTATION followed by name of work.**
9. Payment Terms- 100% payment will be passed on satisfactory completion of works at site
10. The successful bidder shall execute an agreement in Kerala stamp paper with applicable Security Deposit for the fulfillment of contract. The security deposit will be released on expiry of defect liability period.

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 695 033 on or before **11-10-2024, 2:30 PM.**

If the last date mentioned falls as a holiday or Hartal, the very next working day will be treated as the last date.

Issac Varghese
Chief Engineer

* This document is digitally approved. Hence physical signature is not required

Installation of 40 kVA DG set at KTDC- Aahar Restaurant, Mannarkkadu

Sl No	Qty.	Specifications	Unit	Rate	Amount
1	25	Supply, laying and clamping of 1 no. PVC insulated and PVC sheathed armoured aluminium power cable, 1.1 KV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60cms, making good the damages, colour washing etc. as required. 4 core 35 sq mm with factory made clamp. (Make-Polycab, Finolex, V guard, Havells)	m		
2	50	Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required 4.75 mm copper conductor (6 SWG)	m		
3	3	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required	Nos		
4	2	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4 X 35 sq. mm (32mm)	set		
5	10	Supply and providing GI roof sheeting to DG set with required size GI tubes for purlins, rafter, GI poles including foundation for poles etc complete as required at site	Sq.m		
6	10	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) in foundation of pump, DG set etc including form work etc as required.	Cum		
7	1	Charges for removing the interlock tiles for providing foundation for DG set and to dig earth pit from required positions and re lay in positions required at site etc complete	LS		

8	1	Charges for preparation of schematic drawing and obtaining sanction from electrical inspectorate and provide the total connected load to KSEB electrical section and regularize the load.(Statutory fees will be borne by KTDC)	LS		
9	25	Supply & laying 4CX2.5 Sqmm UG 2XFY,PVC insulated and PVC sheathed Copper conductor armoured Power / Control cable of 1.1 KV grade of the following sizes through trench/wall/ ceiling.	m		
10	2	Supplying and making end termination with brass compression gland and copper lugs for following size of PVC insulated and PVC sheathed / XLPE copper conductor cable of 1.1 KV grade as required. 4 X 2.5 sq. mm (Make-Polycab, Finolex, V guard, Havells)	set		
11	10	Supply, fabrication and installation of required dia Class B GI pipe for extension of exhaust pipe including required bends etc complete as required at site. The pipe shall be painted with aluminium paint of one coat.	m		
TOTAL (Inclusive of GST& freight)					