

KTDC/HN/Maintenance/271/2024

04/01/2024

QUOTATION NOTICE

Sub: Rectification works of Nandanam, Guruvayoor – reg

Ref: AE (C)/KTDC.EW-TVM/10653/Nandanam – GVR/2023 dated 23/12/2023

Competitive quotations are invited from PWD/CPWD/Public Sector registered eligible licensed contractors for Rectification works of Nandanam, Guruvayoor.

Sl No	Qty	Unit	Description	Rate	Amount (Rs)
1	68.000	Sqm	Chipping of unsound/weak concrete material from slabs, beams, columns etc. with manual Chisel and/ or by standard power driven percussion type or of approved make including tapering of all edges, making square shoulders of cavities including cleaning the exposed concrete surface and reinforcement with wire brushes etc. disposal of debris for all lead and lifts all complete as per direction of Engineer – in Charge 50 mm average thickness		

2	68.000	Sqm	Providing, mixing and applying SBR polymer (of approved make) modified Cement mortar in proportion of 1:4 (1 cement: 4 graded coarse sand with polymer minimum 2% by wt. of cement used) as per specifications and directions of Engineer-in-charge. Note: Measurement and payment: The pre-measurement of thickness shall be done just after the surface preparation is completed and Payment under this item shall be made only after proper wet curing has been done and surface has been satisfactorily evaluated by sounding / tapping with a blunt metal instrument and/or the 75mm size cube crushing strength at the end of 28 days to be not less than 30 N/Sqmm ²). 50 mm average thickness in 3 layers.		
3	15.601	Sqm	Providing and fixing hard drawn steel wire fabric of size 75 x 25 mm mesh or other suitable size wire mesh to be fixed & firmly anchored to the concrete surface by means of "L" shaped mild steel shear key welded with existing reinforcement including the cost of materials, labour, tool & plants as approved by Engineer-in-charge.		
4	116.000	Sqm	12 mm cement plaster of mix: 1:4 (1 cement : 4 fine sand)		
5	212.000	Sqm	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer		
6	212.000	Sqm	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (One or more coat applied @ 0.90 ltr/10 sqm).		

7	180.000	sqm	Providing and fixing double scaffolding system (Cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40 mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube chakkus, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and / or pointing and / or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-Charge. Note: - (1)The evaluational area of the scaffolding shall be measured for payment purpose, (2) The payment will be made once only for execution of all items of such works.		
Total amount with GST (18%) – Rs.					

The rate shall be inclusive of all taxes, duties, loading and other incidental expenses and net. The copy of license, PAN, GST proof, Address proof to be attached. The offer in sealed cover shall reach the office of the Manager, Nandanam, KTDC, Guruvayoor – 680101 on or before 31/01/2024 up to 02.00 pm. If the last date mentioned falls as a holiday or Harthal or lock down, the very next working day of Hotel Nandanam, Guruvayoor will be treated as the last date.

Name and full address of the applicant

With mobile number, email address & GST Number

Date : 04/01/24
Place : Guruvayoor

Manager
Nandanam
KTDC Ltd Guruvayoor



Signature with Seal