



Kerala Tourism Development Corporation Limited

(A Government of Kerala Undertaking)

P.B No.5424, Mascot Square, Vikas Bhavan P.O

Thiruvananthapuram –695 033, Kerala, India

Phone:++91-471- 2721243/45/48, Fax: 2721249

Website: www.ktdc.com

GST IN 32AABCK0385J1ZP

AE(E)II/KTDC.EW-TVM/226/Aahar-MNDKM&NLPRA/2021

10-05-2023

SHORT RE-QUOTATION NOTICE

Sub: - KTDC – Aahaar restaurant, Mundakkayam- Electrical rectification works and other allied works in connection with obtaining energization sanction for DG set – reg.

Competitive offers are invited from eligible contractors for the Electrical rectification works and other allied works in connection with obtaining energization sanction for DG set at KTDC- Aahaar restaurant, Mundakkayam as per the schedule attached and the following terms and conditions.

Terms & Conditions

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
2. All statutory deductions will be deducted from the bill and exemptions if any shall be informed with supporting documents.
3. The bidders shall have valid B grade contractor license with supervisor permits demanded by Kerala state Electricity Licensing Board.
4. The work shall be carried out in consultation with the KTDC officials.
5. The work shall be completed within 15 days from the date of receipt of order.
6. The work has to be planned & completed without affecting the normal functioning of the Hotel.
7. All the works are to be carried out with good workmanship as per the latest code of practice in accordance with the rules and regulation of the Kerala State Electrical Inspectorate.
8. The Materials used for the work shall be from the approved make of materials mentioned in BOQ.
9. Payment Terms-100% payment will be released on full completion of all works at site.

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 695 033 on or before **20-05-2023, 2.30 PM.**

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.

Issac Varghese
Chief Engineer

* This document is digitally approved. Hence physical signature is not required

**ELECTRICAL RECTIFICATION WORKS AND OTHER ALLIED WORKS IN CONNECTION WITH
OBTAINING ENERGISATION SANCTION FOR DG SET AT KTDC- AAHAAR RESTAURANT,
MUNDAKKAYAM**

Sl. No.	Qty.	Description	Rate	Unit	Amount
1	1	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415 volts, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 amps tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCB's (but without MCB's and incomer) as required. (Note: - Vertical type MCB TPDB is normally used where 3 phase outlets are required. 4 way (4 + 12), Double door		Nos.	
2	5	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole		Nos.	
3	2	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Triple pole		Nos.	
4	1	Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. 40 Amps		Nos.	
5	1	Supplying and fixing following rating, four pole, (three phase and neutral), 415 volts, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required. 40 Amps		Nos.	
6	10	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.		m	

		4 x 6 sq. mm.			
7	10	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required. 25 mm		m	
8	1	Supply and providing four pole enclosure suitable for fixing 4P MCBs/ISOLATORS		Nos.	
9	1	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required		Nos.	
10	10	Supply and providing GI roof sheeting to DG set with required size GI tubes for purlins, rafter, GI poles including foundation for poles etc. complete as required at site		Sq.m.	
11	2	Supply and Providing 6mm thick electrical grade rubber mat (2m x 1m) in front of LT panels.		Nos.	
12	6	Supply, fabrication and installation of 3 inch dia Class B GI pipe for extension of exhaust pipe of 20 kVA DG set including required bends etc. complete as required at site. The pipe shall be painted with aluminium paint of one coat.		m	
		TOTAL AMOUNT (inclusive of all taxes & freight)			

Issac Varghese
Chief Engineer