

Kerala Tourism Development Corporation Ltd.

Mangattuparamba, Kannur -670567

Ph: 04972780220, 29333330, 9400008685, 9400008739 E-mail:folkland@ktdc.com, Website:www.ktdc.com

QUOTATION NOTICE

KTDC /Folkland/73/2024

05.06.2024

Sub: KTDC Development of parking area and compound wall at Folkland, Kannur - reg-

Competitive quotations are invited from PWD/CPWD/PublicSector registered eligible licensed contractors for the Development of parking area and compound wall at Folkland, Kannur as per the schedule of work attached herewith.

The rate shall be inclusive of all taxes, duties, loading and other incidental expenses and net. The copy of license, PAN, GST proof, Address proof to be attached.

The offer with name, address, signature and mobile number of the tenderer in sealed cover shall reach the Manager, KTDC Folk Land, Kannur University Campus (po), Mangattuparamba, Kannur -670567 on or before 15/06/2024 up to 2pm & the quotation will be opened at 2.30pm on the same day.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.

Manager

Folk Land Parassinikadavu

KTDC Ltd.

Manager
Folk Land
Mangattuparamba
Kannur

SL.	QTY	UNIT	DESCRIPTION	RATE	AMOUNT (Rs)
1.	639.125	Sqm	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-incharge. (Old CC paver blocks shall be supplied by the department free of cost.)		
2.	13.684	Cum	Laterate masonry with neatly dressed laterate stone of size $40x20x15cm$ or nearest size in cement mortar 1:6 for super structure above plinth level up to floor two level including all cost of materials, labour charges etc		
3.	45.00	Cum	Filling with contractor own earth (excluding rock) in open areas in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m as per direction of site Engineer-incharge		
4.	6.955	Cum	Demolishing stone rubble masonry manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer -inCharges:In cement mortar		
5.	4.800	Cum	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with: Cement mortar 1:6 (1 cement : 6 coarse sand) with departmental stone available at site		
6.	0.036	Cum	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size)	5	

Name and full address of the applicant

with mobile number, email address & GST Number

Date: 05.06.2024

Place: Mangattuparamba

Signature with Seal

Manager
Folk Land
Mangattuparamba
Kannur