



Kerala Tourism Development Corporation Limited

(A Government of Kerala Undertaking)
P.B No.5424, Mascot Square, Vikas Bhavan P.O,
Thiruvananthapuram –695 033, Kerala, India
Phone:++91-471- 2721243/45/48, Fax: 2721249
Website: www.ktdc.com

AE(E)II/KTDC.EW-TVM/642/RBP-Pullurampara-DG Set/2019

18.06.2022

QUOTATION NOTICE

Sub: - KTDC – Restaurant & Beer parlour, Pullurampara - Installation of 15 kVA DG set –
Quotation Notice – reg.

Competitive offers are invited from reputed firms for the installation of the supplied 15 kVA DG set at KTDC- Restaurant & Beer parlour, Pullurampara as per the schedule attached and the following terms and conditions.

Sl. No.	Name of Work	Time of completion	Eligibility
1	Installation of the supplied 15 kVA DG set at KTDC – Restaurant & Beer parlour, Pullurampara	20 days	Eligible contractors with required scope and those who have executed the installation of same or higher capacity DG sets in past three years. Proof of valid contract license, supervisor permit and details of experience shall be submitted along with offer

Terms & Conditions

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
2. All statutory deductions will be deducted from the bill and exemptions if any shall be informed with supporting documents.
3. The bidders shall have valid license and required scope demanded by Kerala state Electricity Licensing Board.
4. The work shall be carried out in consultation with the KTDC officials.
5. The work shall be completed within 20 days from the date of receipt of order.
6. The work has to be planned & completed without affecting the normal functioning of the Hotel.

7. All the works are to be carried out with good workmanship as per the latest code of practice in accordance with the rules and regulation of the Kerala State Electrical Inspectorate.
8. The Materials used for the work shall be from the approved make of materials mentioned in BOQ.
9. Payment Terms:- 100% payment will be released on full completion of all works at site.
10. **The quotations sent through POST, envelope shall be superscripted with the term QUOTATION followed by name of work.**

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 695 033 on or before **27-06-2022, 2:30 PM.**

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.

Issac Varghese
Chief Engineer

* This document is digitally approved. Hence physical signature is not required

INSTALLATION OF SUPPLIED 15kVA DG SET AT KTDC- RESTAURANT & BEER PARLOUR, PULLURAMPARA					
Sl. No.	Qty.	Description	Rate	Unit	Amount
1	15	Supply, laying and clamping of 1 no. PVC insulated and PVC sheathed armoured aluminium power cable, 1.1 KV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60cms, making good the damages , colour washing etc. as required.4 core 10 sq.mm. with factory made clamp (Make- Havells, Finolex, Polycab, Gloster)		m	
2	20	Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required. 3.15 mm copper conductor (10 SWG)		m	
3	3	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/coke and salt as required		set	
4	1	Supply and Installation of 63A 4 pole change over switch in SS enclosure (Make:- L&T, Siemens, Schneider)		Nos.	
5	1	Preparation and submission of latest scheme drawings,required design and calculations to the Electrical Inspectorate including all MV additions recently made and obtaining approval, arranging inspection for entire installation, obtaining sanction orders for the electrical installation, complete (without statutory expenses)		LS	
		TOTAL (Inclusive of all taxes & freight)			

Issac Varghese
Chief Engineer