



Kerala Tourism Development Corporation Ltd

(A Government of Kerala Undertaking)

Engineering Wing, Mascot Square, Thiruvananthapuram -695 033

Phone: 2318976, 2721243 Fax: ++91-471-2316168

E-mail: mechanical@ktdc.com, website: www.ktdc.com

KTDC/EW/MECH-12-C3/21152/OTH/VKM-BUS/12/2021

02/06/2021

QUOTATION NOTICE

Competitive offers are invited from eligible and reputed contractors/firms for the Supply, installation, testing and commissioning of single phase hi-wall inverter type split air conditioning units in at KTDC-Motel Araam, Vaikom as per the schedule attached and the following terms and conditions.

Terms & Conditions

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site.
2. No rate escalation will be allowed under any circumstances.
3. The makes of AC units shall be from the approved makes mentioned in the schedule.
4. The offer shall be valid for 30 days from the last date of submission of offers.
5. The work shall be completed within 15 days.
6. The warranty period of the supplied items should be a **minimum of 1 year** from the date of testing and commissioning and the actual warranty period of Air conditioner and its sub assemblies as compressor and etc shall be clearly indicated in the offer.
7. All resources (Men, Material, tools & equipments, power, fuel consumables, scaffoldings etc) if required has to be arranged by the firm.
8. All statutory deduction will be deducted from the bill and exemption if any shall be informed with supporting documents.
9. The invoice shall be in GST format with GST numbers of both supplier and receiver to enabling availing credit inputs.
10. KTDC reserves the right to reject any or all quotations and cancel the quotationer process without assigning any reasons.
11. The leaflet bearing the complete technical specifications of the product shall be enclosed along with the offer.
12. Payment Terms- 100% payment will be passed on satisfactory supply, Installation, testing and commissioning of equipments at site with 5% retension for the performance guarantee period.
13. The successful bidder shall execute an agreement in Kerala stamp paper worth Rs. 200/- with a Security Deposit of 5% of contract value for the fulfillment of contract, if the contract value is over Rs.1.00 Lakh. The security deposit will be considered as retension for the performance guarantee period and shall be released on expiry of defect liability period.

14. The work shall be carried out observing Covid-19 protocol issued by statutory authorities from time to time.

The offer shall reach the office of the Executive Engineer (Mechanical), Kerala Tourism Development Corporation Limited, Corporate office, Mascot square, Trivandrum on or before **1.00 PM 16/06/2021** superscribing the name of the work on the cover. **The quotations will be opened on the same day at 3.30 PM.** Further details if required can be had from the office of the Executive Engineer (Mechanical) office hours upto **15/06/2021**.

If the last date mentioned falls as Holiday or Harthal, the very next working day will be treated as the last date / opening date.

A handwritten signature in blue ink, reading "Uday Mathew", with a horizontal line underneath it.

EXECUTIVE ENGINEER (MECHANICAL)

**SUPPLY, INSTALLATION, TESTING AND COMMISSIONING SINGLE PHASE HI-WALL INVERTER TYPE SPLIT AIR CONDITIONING UNITS IN AT
KTDC-MOTEL ARAAM, VAIKOM**

Sl. No.	Qty	Description	Rate	Unit	Amount
1		Supply, Installation, testing and commissioning of inverter type full copper (Condensor & evaporator coils) Split type High wall mounted Air Conditioner unit with cordless remote of following ratings including fixing of Indoor & outdoor units, initial gas charging as per manufacturer standards, giving power connection to nearest Power plug point / MCS with 16A plug top, connecting indoor and outdoor units using hard drawn copper refrigerant pipes insulated with nitrile rubber or equivalent material of minimum 3 mtrs, PVC insulated flexible copper cable of minimum 3 meters as per original manufacturers standards, necessary drain water line using 20mm PVC pipe minimum 3 mtrs. Necessary opening on wall shall be made for drawing refrigerant / power/ drain lines and shall be restored to normal using cement plastering. (Drain pipe line shall be properly fixed and clamped to line and level as per the direction of site engineer in charge). Approved Make: Voltas, L.G, Blue star, Samsung or equivalent.			
1.a	2	1.5TR Capacity inverter type 5 star rated working on single phase 240V, 50Hz +/- 1% AC supply of good quality and approved make		Nos	
2	10	Supply & laying additional refrigerant lines (Both suction & discharge) using hard drawn copper pipe of the suitable sizes recommended by the manufacturer for 1.5TR AC unit including nitrile rubber thermal insulation of good quality to extend the refrigerant gas connection till outdoor unit as required at site.		m	
3	10	Supply & erecting additional 20mm PVC drain piping of good quality to extend water drain connection till nearest silt terminal as required at site.		m	

4	20	Supply & drawing additional control cable of suitable size recommended by the manufacturer between indoor and outdoor unit.		m	
5	2	Supply & providing wall mounting type 4 kVA Voltage Stabilizer designed for Air conditioning load working on 240V, 50Hz Single Phase AC supply to feed output voltage at +/- 10% tolerance with automatic low voltage & high voltage cutoff, built in thermal overload protection, powder coated enclosure etc. complete good quality and approved make and giving connection. <i>(Approved make: Vguard or equivalent reputed brand)</i>		Nos	
6	2	Supply & fixing supporting stand / clamp for fixing the outdoor unit using suitable support bars /anchor bolts and safety hook up etc. including all accessories etc. complete.		Set	
		TOTAL			

The rate shall be inclusive of GST.