



Kerala Tourism Development Corporation Limited

(A Government of Kerala Undertaking)

P.B No.5424, Mascot Square, Vikas Bhavan P.O

Thiruvananthapuram –695 033, Kerala, India

Phone:++91-471- 2721243/45/48, Fax: 2721249

Website: www.ktdc.com

GST IN 32AABCK0385J1ZP

AE(E)II/KTDC.EW-TVM/667/GC-TVM-Ventilation/2023

27-06-2023

SHORT QUOTATION NOTICE

Sub: - KTDC –Grand Chaithram, Trivandrum- Supply, Installation, Testing and Commissioning of Fresh air, Exhaust, Hood and ducting works – Short Quotation Notice – reg.

Competitive offers are invited from eligible contractors for the supply, installation, testing and commissioning of fresh air, exhaust, hood and ducting works at KTDC Grand Chaithram, Trivandrum as per the schedule attached and the following terms and conditions.

Terms & Conditions

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
2. All statutory deductions including service tax will be deducted and exemption if any shall be informed with supporting documents.
3. The bidders are requested to visit the site before quoting to have a study of the site condition and nature of work.
4. The bidder shall need to submit detailed duct drawing before the commencement of work.
5. Contractor will be responsible for all the works and should submit and check all designs. The contractor should point out the changes if any, at the time of approval.
6. The work has to be planned & completed without affecting the normal functioning of the Hotel and the work should be carried out in consultation with the KTDC officials and should progress in accordance with other ongoing works if any.
7. The work shall be completed within 20 days from the date of work order.
8. All the works are to be carried out with good workmanship as per the latest code of practice in accordance with the relevant standard and should depute a full-time supervisor for the supervision of work.

9. The bidders should give their offer in the prescribed BOQ uploaded. Offers submitted other than in the prescribed format will be liable to be rejected and has no claim even if they are the lowest.
10. The bidders should have experience in executing similar works and should attach experience certificate of one similar work whose value not less than 5 lakh or two similar works each costing not less than Rs. 2.5 Lakhs.
11. The proof of experience must be a work completion certificate from the client. Bill, work order (except the work done with KTDC) will not consider as work completion documents.
12. All electrical works involved shall be in accordance with the Kerala State Electrical Inspectorate rules and regulation. Necessary approval, drawing etc. are to be made by the selected contractor without any additional cost. Any modification suggested by the authorities shall be carried out at no extra cost.
13. Details of after sales service facility provided/available have to be indicated along with the offer.
14. All required documents such as as-built drawing etc. are to be given at the end of satisfactory commissioning of the system.
15. The contractor has to make necessary drawing, layout, design calculations etc. for approvals from the concern authorities.
16. Payment Terms: - 100% payment will be released on full completion of all works at site.
17. The successful bidder shall execute an agreement in Kerala stamp paper with applicable Security Deposit for the fulfillment of contract. The security deposit will be released on expiry of defect liability period.
18. The Quotations sent through POST, envelope shall be superscripted with the term QUOTATION followed by the name of work.

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 695 033 on or before **10-07-2023, 2:30 PM.**

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.

Sikha Surendran IAS
Managing Director

* This document is digitally approved. Hence physical signature is not required

SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF FRESH AIR, EXHAUST, HOOD AND DUCTING WORKS AT KTDC-GRAND CHAITHRAM, TRIVANDRUM					
Sl No	Qty	Description	Rate	Unit	Amount
1	1	Supply and installation of axial flow fan 1 H.P/3 phase (750 watts) for fresh air circulation. Including necessary structural support and vibration elimination connections as required		Nos	
2	1	Supply and installation of axial flow fan 2 H.P/3 phase (1500 watts) for exhaust. Including necessary structural support and vibration elimination connections as required.		Nos	
3	1	Supply, installation and commisiointing of Exhaust Hood - Island type made of 22 SWG SS 304 sheet and filters with 26 SWG SS 304 Sheet including all necessary structural supports required at site SS Hood size (3 Burner) : 200x75cm		Nos	
4	1	Supply, installation and commisiointing of Exhaust Hood - Island type made of 22 SWG SS 304 sheet and filters with 26 SWG SS 304 Sheet including all necessary structural supports required at site -SS Hood size (bulk cooking-3 Nos) : 210x90cm		Nos	
5	1	Supply, installation and commisiointing of Exhaust Hood - Island type made of 22 SWG SS 304 sheet and filters with 26 SWG SS 304 Sheet including all necessary structural supports required at site -SS Hood size (2 nos of Hot plate) : 210x90 cm		Nos	
6	1	Supply, installation and commisiointing of Exhaust Hood - Island type made of 22 SWG SS 304 sheet and filters with 26 SWG SS 304 Sheet including all necessary structural supports required at site -SS Hood size (3 Nos of 3 Burner) : 240 x 225 cm		Nos	

7	130	Supply, Installation, balancing and commissioning of fabricated at site GSS sheet metal rectangular / round ducting complete with neoprene rubber gaskets, elbows, splitter dampers, vanes, hangers, supports, etc as per approved drawings and specifications of following sheet thickness complete as required.Site fabricated GSS sheet metal rectangular ducting as per IS 655-2006 for 0.63 mm thick		Sq.m	
8	2	Supplying, fixing testing commissioning of powder coated aluminum grills without volume controlled damper		Sq.m	
Electrical works					
9	50	Supply, laying and clamping of 1 no. PVC insulated and PVC sheathed armoured aluminium power cable, 1.1 KV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60cms, making good the damages , colour washing etc. as required.4 core 4 sq mm with factory made clamp		m	
10	2	S & F Motor starters of the following ratingsThree phase DOL starters for 0.25HP to 7.5 HP motor		Nos	
11	50	Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required2.64 mm GI conductor (12 SWG)		m	
12	20	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required >4 X 4 sq. mm + 1 X 2.5 sq. mm earth wire		m	
TOTAL (Inclusive of all taxes & freight)					

PRESS RELEASE

**KERALA TOURISM DEVELOPMENT CORPORATION LIMITED,
TRIVANDRUM**

QUOTATION NOTICE

**NAME OF WORK: SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF
FRESH AIR, EXHAUST, HOOD AND DUCTING WORKS AT KTDC-GRAND
CHAITHRAM, TRIVANDRUM**

LAST DATE FOR SUBMISSION OF OFFERS: - 10-07-2023, 2:30 PM.

Further Details can be had from:
The Office of the Chief Engineer,
Kerala Tourism Development Corporation Limited,
Mascot Square,
Trivandrum - 695 033
Ph-0471-2721243

OR

website: www.ktdc.com