



Kerala Tourism Development Corporation Limited

(A Government of Kerala Undertaking)

P.B No.5424, Mascot Square, Vikas Bhavan P.O

Thiruvananthapuram -695 033, Kerala, India

Phone:++91-471- 2721243/45/48, Fax: 2721249

Website: www.ktdc.com

GST IN 32AABCK0385J1ZP

KTDC/KGR/ESTT/345/2023

24-06-2024

RE-QUOTATION NOTICE

Sub: - KTDC- Kumarakom Gateway Resort, Thanneermukkom- Supply, installation, testing and commissioning of Incinerator-Quotation.reg.

Competitive offers are invited from reputed firms for supply and providing incinerator system (50kg/Day capacity) at KTDC Kumarakom Gateway Resort, Thanneermukkom as per the schedule attached herewith and the following terms and conditions.

Sl. No.	Name of work	Time of completion	PAC	Eligibility
1	Supply, installation, testing and commissioning of Incinerator (50Kg/Day Capacity) at Kumarakom Gateway Resort, Thanneermukkom.	20 Days	Rs. 1,79,000/- (including GST)	Reputed firms completing two similar works costing not less than 1.8Lakhs. Experience certificate shall be submitted along with the offer.

Terms & Conditions

1. The rate shall be inclusive of GST, duties, loading and unloading charges, transportation, other incidental expenses and net for the work at each site.
2. All statutory deduction will be deducted from the bill and exemption if any shall be informed with supporting documents
3. The leaflet/catalogue of the system shall be submitted along with offer.
4. The quotations sent through POST, envelope shall be superscribed with term QUOTATION followed by name of work.
5. The work shall be completed within 20 days from the date of execution of agreement.

6. The successful firm shall execute an agreement on required value Kerala stamp paper with a security deposit of 5% of the contract value.

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 33 on or before **05-07-2024, 2:30 PM**.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.

Issac Varghese
Chief Engineer

* This document is digitally approved. Hence physical signature is not required

Schedule for the Supply, installation, testing and commissioning of Incinerator at Kumarakom Gateway Resort, Thanneermukkom

Sl No	Qty	Item / Specifications	Unit	Rate	Amount
1	1	Supply of no fuel type 50 Kg/day capacity solid waste disposing incinerator with following specification and having waste loading ash removal provision. Body-MS sheet with 6mm thickness. Incinerator size- Minimum (85 dia.X170 Ht.)cm Fire wall- 4 inch Exhaust Pipe- SS 304 material with 10 ft height of suitable diameter with rain guard. The entire body shall be painted with corrosion resistant material.	No		
2	1	Installation, Testing and commissioning of incinerator at site	No		
3	1	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) in foundation of pump, DG set etc including form work etc as required.	Cum		
Total (Inclusive of GST)					