



Kerala Tourism Development Corporation Ltd
(A Government of Kerala Undertaking)
Engineering Wing, Mascot Square, Thiruvananthapuram -695 033
Phone: 2318976, 2721243 Fax: ++91-471-2316168
E-mail: chiefengineer@ktdc.com website: www.ktdc.com

AE(E)II/KTDC.EW-TVM/667/TEH-Kannur-DGset/2019

18-02-2020

QUOTATION NOTICE

Sub:- KTDC – Tamarind easy Hotel, Kannur –Installation and allied works of supplied of 62 kVA DG Set – Quotation Notice-reg.

Competitive offers are invited from reputed firms for the installation and allied works of supplied 62 kVA DG Set at KTDC – Tamarind easy Hotel, Kannur as per the schedule attached and the following terms and conditions.

Terms & Conditions

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
2. All statutory deductions will be deducted from the bill and exemptions if any shall be informed with supporting documents.
3. The bidders shall have minimum valid B grade contractor license having minimum scope of 50 kW with valid B grade supervisor permit issued by Kerala state Electricity Licensing Board.
4. The work shall be carried out in consultation with the KTDC officials
5. The work shall be completed within 20 days from the date of arrival of DG set at site.
6. The work has to be planned & completed without affecting the normal functioning of the Hotel.
7. All the works are to be carried out with good workmanship as per the latest code of practice in accordance with the rules and regulation of the Kerala State Electrical Inspectorate.
8. Payment Terms-100% payment will be released on full completion of all works at site.
9. The successful bidder shall execute an agreement in Kerala stamp paper worth Rs. 200/- with a Security Deposit of 5% of contract value for the fulfillment of contract. The security deposit will be released on expiry of defect liability period.

The offer shall reach the office of the Chief Engineer, KTDC Ltd., Mascot Square, Trivandrum – 695 033 on or before **28-02-2020, 2.30 PM.**

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.

P.K BABU
CHIEF ENGINEER

[Signature]
Chief Engineer

[Signature]
AE(II)



**INSTALLATION & ALLIED WORKS OF SUPPLIED 62 KVA DG SET AT KTDC-TAMARIND EASY HOTEL,
KANNUR- BOQ**

Sl No	Qty	Description	Rate	Unit	Amount
1		Supply, laying and clamping of 1 no. PVC insulated and PVC sheathed armoured aluminium power cable, 1.1 KV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60cms, making good the damages , colour washing etc. as required. (Approved Makes- V Guard, Polycab, Finolex, RR)			
1.1	10	3.5C X 50 Sq.mm		m	
2	2	Supplying and making end termination with brass compression gland and aluminium lugs for 3.5C x50 Sq.mm size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.		Nos	
3	3	Supply and providing Earthing with G.I. earth pipe 3.0 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required		Nos	
4		Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required			
4.1	50	6.00 mm copper conductor (4 SWG)		m	
5	15	Supply of superior quality copper earth socket for the following size of earth conductor including crimping etc. as required. 6. mm (4 SWG)		Nos	
6	5	Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) in foundation of pump, DG set etc including form work etc as required		Cub.m	
7	5	Supply & providing Aluminium anodised Danger Notice Board of size 200 x 150 mm. with inscriptions (both in English and Malayalam) and conventional Skull and Bone in Red colour at locations as directed by the Engineer in Charge		Nos	

Chief Engineer



8	1	Supply and providing Laminated Electrical Schematic diagram framed and placed in a conspicuous location for clear vision.		Nos	
9	1	Supply and providing First Aid Chart duly framed and placed in a conspicuous location for clear vision.		Nos	
10	4	Supply and Laying 2.00 mm thick, 3.3 kV, Synthetic elastomeric fire retardant insulating sheet in front of panels		Sq.m	
11	3	Supply and providing 9 Litre capacity GI Fire Bucket painted in post office red with primer coat of red oxide and written with white paint 'FIRE' mounted on MS angle frame work/ wall bracket filled with fine sand, painting the bracket/ floor stand including making good the damages, colour washing etc. as required.		set	
12	5	supply and providing ABC type fire extinguisher ISI mark , 4Kg capacity with initial charger and installation brackets.		set	
13	1	Preparation and submission of latest scheme drawings,required design and calculations to the Electrical Inspectorate including all MV additions recently made and obtaining approval, arranging inspection for entire installation, obtaining sanction orders for the electrical installation, complete (without statutory expenses)		LS	
14	1	Charges for Liasioning with KSEB regarding connected load after renovation works and power enhancement procedures if required etc and prepare and submitting all required documents etc complete as required at site (without statutory charges)		LS	
15	1	Charges for dismantling the existing Panel board/Changeover Switch/DB including the related cable connected etc. completely and stacking the same as usable / reusable materials etc. complete.		LS	
Total (Inclusive of all taxes)					

AEE (CE &)

Chief Engineer