



KERALA TOURISM DEVELOPMENT CORPORATION LIMITED

(A Government of Kerala Undertaking)

ROS, Mascot Square, Thiruvananthapuram -695 033

Phone: 2318976, 2721243 Fax: ++91-471-2316168

Email: chiefengineer@ktdc.com website: www.ktdc.com

KTDC/ROS/ Ahaar Kayamkulam/ Roofing work /2021

18-10-2021

QUOTATION NOTICE

Sub:- KTDC – ROOFING WORK OVER THE KITCHEN AREA DUE TO LEAKAGE AT AHAAR RESTAURANT KAYAMKULAM -reg.

Competitive quotations are invited from reputed firms for roofing work over the kitchen area due to leakage at Ahaar restaurant Kayamkulam as specified below.

CIVIL WORKS						
Item no	Qty	unit	Description	Unit	Rate	Amount
1	556.261	kg	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	kg		
2	55.465	sqm	Providing corrugate G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal / vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.0.4 mm thick with zinc coating not less than 275 gm/m ²	sqm		
3	20	sqm	Providing and laying water proofing treatment on roofs of slabs by applying cement slurry mixed with water proofing cement compound consisting of applying : a) after surface preparation, first layer of slurry of cement @ 0.488 kg/ sqm mixed with water proofing cement compound @	sqm		

			0.253 kg/ sqm. laying second layer of fibre glass cloth when the first layer is still green. Overlaps of joints of fibre cloth should not be less than 10 cm. c) third layer of 1.5 mm thickness consisting of slurry of cement @ 1.289 kg/ sqm mixed with water proofing cement compound @ 0.670 kg/sqm and coarse sand @ 1.289 kg/sqm. This will be allowed to air cure for 4 hours followed by water curing for 48 hours. The entire treatment will be taken upto 30 cm on parapet wall and tucked into groove in parapet all around. d) fourth and final layer of brick tilling with cement mortar (which will be paid for separately. For the purpose of measurement the entire treated surface will be measured			
4	30	m	Providing 140 mm split PVC gutter to receive the rain water from roof including necessary fittings such as end cap, middle drop, chain, GI flat clamps, cost, labour, etc. complete as per the direction of engineer in charge	m		
5	30	m	Providing and fixing on wall face PVC rain water pipes 110mm dia 4kg/cm ² , including jointing with solvent, specials, etc	m		
			TOTAL			

The rate shall be inclusive of all taxes, duties, loading and other incidental expenses and net for the work at Ahaar restaurant Kayamkulam.

The offer shall reach the office of the Manager Regional Office South, Kerala Tourism Development Corporation Limited, Mascot Square, Trivandrum – 33 on or before **25-10-2021 up to 2.30 PM** & the quotation will be opened at **3.30PM** on the same day.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.


MANAGER
 Regional Office South