



Mascot Hotel

(A unit of KTDC Ltd - Government of Kerala undertaking)
Mascot Square, PMG, Thiruvananthapuram - 695 033.
Phone : + + 91 471 2318990, Fax + + 91 471 2317745
E-mail : mascot hotel@ktdc.com Web site : www.ktdc.com

KTDC/MH/EST/QN/22-23/

09-11-2022

Re-Quotation Notice

Sub: – KTDC MASCOT HOTEL, Trivandrum – Supply, installation, testing & commissioning of split AC units in various locations – Short Re- Quotation Notice – reg.

Competitive offers are invited from eligible and reputed firms having valid license for the supply, installation, testing and commissioning of split AC units in Supply, installation, testing & commissioning of split AC units in various locations – Mascot Hotel, Trivandrum as per the schedule attached and the following terms and conditions.

Terms & Conditions

1. The rate shall be inclusive of GST, duties, loading, unloading charges, transportation, other incidental expenses and net for the work at site. No rate escalation will be allowed under any circumstances.
2. All statutory deduction will be deducted from the bill and exemption if any shall be informed with supporting documents.
3. The makes of AC units and stabilizers shall be from the approved makes mentioned in the BOQ.
4. The offer shall be valid for 30 days from the last date of submission of offers.
5. The work shall be carried within 10 days from the date of work order.
6. The warranty period of the supplied items should be a **minimum of 1 year** from the date of testing and commissioning and the actual warranty period of AC, PC Board, compressor and stabilizer etc shall be clearly indicated in the offer.
7. The leaflet bearing the complete technical specifications of the product shall be enclosed along with the offer.
8. **The quotations shall be enclosed and submitted in a sealed envelope on which the name of work shall be clearly superscribed. Otherwise the quotations will be summarily rejected.**
9. Payment Terms: - 100% payment will be passed on satisfactory supply, installation, testing and commissioning of equipments at site
10. The successful bidder shall execute an agreement in Kerala stamp paper worth Rs. 200/- with a Security Deposit (5% of quoted amount) for the fulfillment of contract. The security deposit will be released on expiry of defect liability period.

The offer shall reach the office of The Manager, Mascot Hotel, KTDC Ltd., Mascot Square, Trivandrum -33 on or before **23-11-2022, 2:30 PM** superscribing the name of the work on the cover.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date.



MANAGER



**KTDC –MASCOT HOTEL-Supply, installation, testing & commissioning of Split AC units in
Various Location-Quotation BOQ**

Sl. No.	Qty.	Description	Rate	Unit	Amount
1	2.00	Supply, installation, testing and commissioning of 2TR Inverter type High wall mounted 3 star or above rated Split Air Conditioner unit having copper condenser, stabilizer (V-Guard:-Model No. VG 500 or equivalent), cordless remote, outdoor stand etc. and all fixing accessories including fixing of Indoor & outdoor units, initial gas charging as per manufacturer's standards, giving power connection to nearest power plug point / MCS, connecting indoor and outdoor using hard drawn copper refrigerant pipes insulated with nitrile rubber of suitable thickness of length approximately 3 meters, PVC insulated flexible copper cable of length approximately 3 meters as per original manufacturer standards, necessary drain water line using 20 mm PVC pipe of length approximately 3 metres. Necessary opening on the wall shall be made for drawing refrigerant / power / drain lines and the same shall be restored to normal using cement plastering. (Drain pipe line shall be properly fixed and clamped to line and level as per the direction of authorized maintenance staff in charge). Make:- Daikin, Carrier, Bluestar or Equivalent)- Location- Bakery & Kitchen Pantry		Each	

2	1	<p>Supply, installation, testing and commissioning of 1.5 TR Split type High wall mounted Cordless remote 3 star or above rated inverter type Air Conditioner unit with required capacity stabilizer (Make: V Guard-VG400) and all fixing accessories including fixing of Indoor & outdoor units, initial gas charging as per manufacturer standards, giving power connection to nearest Power plug point / MCS, connecting indoor and outdoor units using hard drawn copper refrigerant pipes insulated with nitrile rubber or equivalent material of approximately 3 mtrs, PVC insulated flexible copper cable of approximately 3 meters as per original manufacturer standards, necessary drain water line using 20mm PVC pipe approximately 3 mtrs. Necessary opening on wall shall be made for drawing refrigerant / power / drain lines and shall be restored to normal using cement plastering. (Drain pipe line shall be properly fixed and clamped to line and level as per the direction of authorized maintenance staff in charge). Make: Blue Star/Daikin/Carrier or equivalent- Location-AM cabin</p>		Each	
3	1	<p>Supply, installation, testing and commissioning of 1.5 TR Split type High wall mounted Cordless remote 3 star or above rated inverter type Air Conditioner unit with required capacity stabilizer (Make: V Guard-VG400) and all fixing accessories including fixing of Indoor & outdoor units, initial gas charging as per manufacturer standards, giving power connection to nearest Power plug point / MCS, connecting indoor and outdoor units using hard drawn copper refrigerant pipes insulated with nitrile rubber or equivalent material of approximately 3 mtrs, PVC insulated flexible copper cable of approximately 3 meters as per original manufacturer standards, necessary drain water line using 20mm PVC pipe approximately 3 mtrs. Necessary opening on wall shall be made for drawing refrigerant / power / drain lines and shall be restored to normal using cement plastering. (Drain pipe line shall be properly fixed and clamped to line and level as per the direction of authorized maintenance staff in charge). Make: Blue Star/Daikin/Carrier or equivalent-Location- Bakery store</p>		Each	

4	3	Supply & providing of additional hard drawn copper refrigerant pipe of required size as per manufacturer's standard with 13mm thick nitrile rubber thermal insulation. (Suction/ liquid line will not be measured separately). For 2 tr AC		M	
5	2	Supply & providing of additional hard drawn copper refrigerant pipe of required size as per manufacturer's standard with 13mm thick nitrile rubber thermal insulation. (Suction/ liquid line will not be measured separately). For 1.5 tr and 1tr AC		M	
6	5	Supply and laying additional control cable of required size for AC unit as per manufacturer's standard of good quality and reputed brand		M	
7	5	Supply & fixing of additional PVC drain Pipe with proper insulation and U trap		RM	
		TOTAL AMOUNT (inclusive of GST)		Rs.	


 **MANAGER**