



Kerala Tourism Development Corporation Limited
(A Government of Kerala Undertaking)

Engineering Wing, Mascot Square, Thiruvananthapuram -695 033

Phone: 2318976, 2721243 Fax: ++91-471-2316168

Email: chiefengineer@ktdc.com website: www.ktdc.com

CE/KTDC.EW-TVM/192/GP-Ponmudi/RR/2020

02/03/2020

QUOTATION NOTICE

Sub:- KTDC – Providing Aluminum sheet below the tiled roof for preventing rain water leakage at Golden Peak, Ponmudi - reg.

Competitive quotations are invited from eligible licenced contractors for Providing Aluminum sheet below the tiled roof for preventing rain water leakage at Golden Peak, Ponmudi as specified below.

The contractor shall have valid firm / company /Co-operative-society registration in Govt and have satisfactorily executed at least two – 3 star hotel / resort project in Govt / private sector with financial capability not less than Rs 10 Lakhs and the same shall be certified by a person not below the rank of executive engineer in the last 5 years.

Sl. No	Qty	Unit	Description	Rate	Amount (Rs)
1	70	sqm	Dismantling and removing mangalore tiles over roof including ridges, hips, valley sheet, and wind ties etc complete including stacking of serviceable material within a distance of 150m and disposal of unserviceable material		
2	200	Mtr	Dismantling tubular steel work for purline including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking carefully within 50 meters lead.		
3	100	Nos	Supplying roof pressed clay tile ridge (mangalore tile) of 20mm thickness and of approved pattern including all conveyance.		
4	350	Nos	Supplying roof pressed clay tile (mangalore tile) of 20mm nominal thickness and of approved size and as per approved pattern including cost and conveyance.		
5	70	Sqm	Providing and fixing 0.80mm thick aluminum plain sheet over the steel truss. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal / vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.		
6	75	kg	Steel work for purlin /single section with GI pipes including cutting, hoisting, fixing in position and applying a priming coat of approved		

Handwritten signature
Chief Engineer



			steel primer, including welding and bolted with special shaped washers etc. complete		
7	200	Mtr	Refixing the purlin / single section with MS tubular sections using with departmental MS sections (Dismantled and stacked) including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete		
8	65	Kg	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing position and applying a priming coat of approved steel primer all complete		
9	500	kg	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc. including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete Hot finished seamless type tubes		
10	24	Sqm	Providing and fixing plain multipurpose cement board (High Pressure Steam Curved) as per IS : 14862, with suitable screws for fibre cement board in ceiling etc. complete (Frame work to be paid separately) : 6mm thick cement bonded wood particle board as per IS : 14276		
11	24	Sqm	Applying priming coat : with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel work (second coat)		
12	24	Sqm	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : two or more coats on new work		
13	70	sqm	Providing and fixing on roof pressed departmental (dismantled and stacked new and old) clay tile (mangalore tile) on steel frame work complete (steel frame work to be paid separately)		
14	70	Mtr	Providing and laying on roof pressed departmental (dismantled and stacked new and old tiles) clay tile ridge (mangalore tile) on steel frame work set in CM. 1:6 including finishing edge etc. complete (steel frame work to be paid separately)		
15	15	Mtr	Cement mortar 1:6 bordering to tiled roof about 65 cm ² in section etc. complete		
16	7	Nos	Supplying tarpaulin sheet in the cottage premises		
			TOTAL		

Chief Engineer



The rate shall be inclusive of all taxes, duties, loading and other incidental expenses and net.

The offer shall reach the office of the Chief Engineer, Kerala Tourism Development Corporation Limited, Mascot Square, Trivandrum – 33 on or before **10/03/2020 up to 2.30 PM** & the quotation will be opened **at 3.30PM** on the same day.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.

~~Signature~~
02/03/2020
P.K.BABU
CHIEF ENGINEER KTDC

Handwritten initials in purple and blue ink.