



Aranya Nivas

(A unit of KTDC Ltd-Government of Kerala undertaking)

Periyar Tiger Reserve, Thekkady, Idukki-685509, Kerala

Phone +91-4868-250111 Fax: +91- 04869-222282

E-mail: aranyanivas@ktdc.com

Web site: www.ktdc.com

KTDC/ANH/EST/QN/214 /2024-25

09.09.2024

RE- QUOTATION NOTICE

Competitive quotations in sealed covers are invited from eligible licensed contractors and licensed established firm having GSTIN and PAN No. for the work noted below as per the scheduled/BOQ attached.

SL No	Name of work	Time of Completion
1	Construction of new soak pit for the STP at Aranya Nivas, Thekkady	1 month

General Conditions

7. The rate shall be inclusive of GST, all taxes, duties, loading, unloading and other incidental expenses and net.
8. The bidder shall visit/ inspect the site before submitting the quotation.
9. The successful bidder shall obey the rules and regulation of forest department/ Periyar tiger reserve authority.
10. The successful bidder will have to deposit an amount equal to 5% of the total quoted amount as security deposit and also execute agreement in stamp paper worth Rs.200/- for the due fulfillment of the contract.
11. The successful bidder shall obtain approvals for the materials and detail of proposed work from the engineering officials of KTDC.
12. The work should be completed as per the accompanied specification within **1 month** of receipt of work order/executing agreement.

The quotation will be available from **09/09/2024 10.00 am** and the offer shall reach the office of the Manager, Aranya Nivas KTDC Ltd, Thekkady on or before **19/09/2024 up to 2.30 PM** & the quotation will be opened **at 3.30PM** on the same day.

The Management reserves the right to reject any or all quotations without assigning any reason thereof.


If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.


MANAGER



BOQ OF THE WORK- Construction of Soak Pit for the STP at Aranya Nivas, Thekkady

SL No	Qty	Unit	Description	Rate With Tax	Amount
1	1	no	19.32.1 Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design. With common burntclay F.P.S. (non modular) bricks of class designation 7.5		
2	40	m	50.18.9.9.1 Providing and fixing PVC pipes including jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of Joints complete as per direction of engineer in charge. 110 mm dia 6Kgf/cm ²		


Manager
Aranya Nivas
Thekkady - 685 001