Lake Palace
(A unit of KTDC Ltd-Government of Kerala undertaking)
Periyar Tiger Reserve, Thekkady, Idukki-685509, Kerala
Phone +91-4868-250111 Fax: +91- 04869-222282
E-mail:**lakepalace@ktdc.com**
Web site: www.ktdc.com

KTDC/LP/EST/QN/ 110 /2024-25 29.08.2024

SHORT QUOTATION NOTICE

Competitive quotations in sealed covers are invited from eligible licensed contractors and licensed established firm having GSTIN and PAN No. for the work noted below as per the scheduled/BOQ attached.

SL No	Name of work	Time of Completion
1	Construction of new soak pit & bar screen and oil & grease trap chamber for waste water treatment at Lake Palace, Thekkady	1 month

General Conditions

1. The rate shall be inclusive of GST, all taxes, duties, loading, unloading and other incidental expenses and net.
2. The bidder shall visit/ inspect the site before submitting the quotation.
3. The successful bidder shall obey the rules and regulation of forest department/ Periyar tiger reserve authority.
4. The successful bidder will have to deposit an amount equal to 5% of the total quoted amount as security deposit and also execute agreement in stamp paper worth Rs.200/- for the due fulfillment of the contract.
5. The successful bidder shall obtain approvals for the materials and detail of proposed work from the engineering officials of KTDC.
6. The work should be completed as per the accompanied specification within **1 month** of receipt of work order/executing agreement.

The quotation BOQ will be available from **30/08/2024 10.00 am** and the offer shall reach the office of the Manager, Lake Palace, KTDC ltd, Thekkady on or before **05/09/2024 up to 2.30 PM** & the quotation will be opened **at 3.30PM** on the same day.

The Management reserves the right to reject any or all quotations without assigning any reason thereof.

If the last date mentioned falls as a holiday or Harthal, the very next working day will be treated as the last date/ opening date.

MANAGER
29/8

BOQ OF THE WORK- Construction of Soak Pit and Bar screen chamber at Lake Palace, Thekkady

SL No	Qty	Unit	Description	Rate With Tax	Amount
1	2	no	19.32.1 Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricksand S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design.With common burnt clay F.P.S. (non modular) bricks of class designation 7.5		
2	4	m	50.18.9.9.1 Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching,refilling & testing of Joints complete as per direction of engineer in charge.110 mm dia 6Kgf/cm2		
3	1	no	od97296/2024_2025 Screen chamber of size 60x60, minimum 8mm hole (with lid/ opening at top) including materials, labour etc.		
4	1	no	od97320/2024_2025 Supply and installation of grease trap for the kitchen. The work includes all material, labour, conveyanceetc. all complete as per the direction of engineer in charge		
5	2.5	cum	2.6.1 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas(exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed.All kinds of soil		
6	5	m	50.18.9.9.2 Providing and fixing PVC pipes includes joints of pipes with one step PVC solvent cement, trenching,refilling & testing of joints complete as per direction of Engineer in CHarge. 110 mm dia 4 Kg/cm2		

MANAGER
LAKE
KTDC THE

OFFICE OF THE MANAGER
LAKE PALACE
KTDC
THEKKADY